

WHITMAN COUNTY PUBLIC WORKS SMALL WORKS WORKSHEET

PROJECT NAME: 2017 Bridge Lumber Supplies

DESCRIPTION: (Materials, Supplies, Equipment)

See attached specifications

All materials, equipment and supply costs, plus tax, should be included in the quote. **QUOTE MUST BE FOB COLFAX**

Initial

Delivery must be by: Thursday, June 15, 2017 by 5:00 p.m.

NO FRIDAY DELIVERIES

Initial

QUOTES MUST BE RETURNED BY: Thursday, April 20, 2017 by 5:00 p.m.

Contact: Phil Meyer – Ext. 5203

Phil.Meyer@co.whitman.wa.us

Whitman County Public Works: (509) 397-4622 FAX (509) 397-6210

WHITMAN COUNTY IS REQUESTING QUOTES FOR 2017 BRIDGE LUMBER SUPPLIES

ITEM: 2017 Bridge Lumber and Sign Posts as Specified

F.O.B. Colfax, Washington

SPECIFICATIONS: All of the lumber shall be No. 1 or better structural grade Douglas Fir

All treated timber will be treated in accordance with AWPA Standards of the State of Washington Standard Specifications Manual of 2016 (English) for lumber and timbers, for bridges, structural members, decking, etc.

BRIDGE LUMBER

UNTREATED DOUGLAS FIR NO. 1 ROUGH

| QUANTITY | SIZE | DESCRIPTION | EACH | TOTAL |
|-----------------|----------------|-----------------|------|-------|
| 64 or two units | 4" x 12" x 20' | Untreated Rough | | |
| 32 or one unit | 4" x 12" x 26' | Untreated Rough | | |

TREATED DOUGLAS FIR NO. 1 ROUGH

| QUANTITY | SIZE | DESCRIPTION | EACH | TOTAL |
|----------|----------------|-------------|------|-------|
| 12 | 5" x 18" x 25' | Treated | | |
| 12 | 5" x 18" x 14' | Treated | | |

TREATED DOUGLAS FIR NO. 1 S4S FREE OF HEART

| QUANTITY | SIZE | DESCRIPTION | EACH | TOTAL |
|-------------------------------|---------------|-------------|------|-------|
| 3 units or somewhere near 300 | 4" x 4" x 14' | Treated S4S | | |

ALL LUMBER MUST BE BANDED TOGETHER BY SIZE IN UNITS OR BY QUANTITIES ORDERED.

Sub-Total _____

Washington State Sales Tax _____

TOTAL _____

Company: _____ **Contact Person:** _____