

**WHITMAN COUNTY CAROTHERS ROAD SOLID WASTE FACILITY**  
**MRW BUILDING REMODEL PROJECT (XEW36)**  
**REQUEST FOR QUOTE FOR ELECTRICAL CONTRACTORS**

**PROJECT OVERVIEW:**

Whitman County (“Owner”) is requesting vendor quotes from qualified Electricians licensed in the State of Washington to perform electrical and communications services for the Moderate Risk Waste (MRW) Building Remodel at the Carothers Road Solid Waste Facility (“Project”).

The purpose of the project is to remodel and expand the existing MRW Building. The project will modernize the building, expand and increase building operations, and bring the facility into code by providing sufficient ventilation, secondary containment, combustible gas detection, dry-chemical fire suppression, and a new safety shower/eye wash station supplied by tepid water.

A General Contractor will be hired separately by the Owner for this Project and will perform all work except for electrical and communications. The General Contractor has the responsibility for limiting the amount of downtime for Owner’s operations and maintaining access into and out of the site during the entire duration of the Project as to not disrupt day-to-day facility operations. The Electrician must coordinate all work to ensure that they do not delay or disrupt the General Contractor’s work or Owner’s operations.

The General Contractor’s scope of work includes, but is not limited to:

- Coordinating with the Owner’s electrician.
- Demolition of existing utilities and services within the existing MRW Building, except for electrical.
- Site/Yard work including excavation for building expansions on the north and south ends, storm drain installation, gravel surfacing, replacing yard utilities (except for electrical), and other general site work.
- Concrete work for new housekeeping (utility pads), a walkway, extension of the pull-through slab, and concrete work related to the building expansion for footings, walls, and floor.
- Carpentry and masonry work for the building expansion and improvements within existing spaces.
- Metals and special architectural features of the project.

The anticipated notice to proceed (NTP) for the General Contractor will be no later than May 18, 2020. Work is required to be substantially complete no later than 120 calendar days after NTP with final completion no later than 30 calendar days after substantial completion. The Electrician will be required to work within these timeframes.

**ELECTRICIAN’S SCOPE OF WORK:**

The Contract Documents for the Project accompany this Request for Quote (RFQ). These documents have been issued to solicit bids from General Contractors and have been provided as part of this RFQ for

informational purposes. The electrical and communications specifications and drawings contained in the Contract Documents are included as part of the electrician’s scope of work.

The Electrician’s scope of work includes, but is not limited to:

- Coordinating with the general contractor and securing all permits and L&I certifications for the Project.
- Demolition of existing electrical and communications utilities and systems within the existing MRW Building and the yard.
- Replacing electrical and communications systems for reconnection to the MRW Building and the nearby Combustible Storage Building.
- Connecting electrical service to the new Avista transformer pad with CT enclosure and metering.
- Replacing all electrical systems, powering all existing, new and provisionary equipment, including the glass crusher, and replacing lighting inside of the remodeled MRW Building to meet all classified space requirements, including explosion-proof.
- Maintain service to the administrative office and scalehouse buildings as needed with temporary service until the permanent services are connected.
- Installing all grounding systems for the Project.
- Installing the fire-alarm system.
- Installing the combustible gas detection system.
- Commissioning of the electrical and communications systems.

**For information concerning this Project or to make an appointment to visit the site, contact David Nails, Solid Waste & Recycling Director at the Carothers Road Solid Waste Facility – (509) 334-2400 or email Dave.Nails@whitmancounty.net.**

**SCHEDULE/TIMELINE:**

Vendors quotes must be emailed to **Brandon Johnson (Brandon.Johnson@whitmancounty.net)** no later than 10 am local time on April 20, 2020. Upon receipt, Brandon will email back to the vendor that he has received the quote. If the vendor does not receive an email, they must call **Brandon at (509) 397-5216** to receive acknowledgment that it has been received. It is the vendor’s responsibility that is issuing a quote to ensure that their quote is received on time. No bid bond is required.

**QUOTE:**

Electricians that are interested in providing a quote are encouraged to visit the site to become familiar with the site conditions and the general elements of the Project.

All materials, equipment, and labor for providing the electrical and communications services.	\$ _____
Washington State Sales Tax	\$ _____
Total	\$ _____

Date: \_\_\_\_\_

Company: \_\_\_\_\_

Address: \_\_\_\_\_

\_\_\_\_\_

Phone: \_\_\_\_\_ Fax: \_\_\_\_\_

Email: \_\_\_\_\_

Signature: \_\_\_\_\_

Title: \_\_\_\_\_