

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

August 24, 2015

ATTENTION: ALL BIDDERS AND PLAN HOLDERS

Countywide Overlays 3
C.R.P.'s No. 0017-2, 0025-3 & 2500-8
STPR-Z938(003)

ADDENDUM No. 1

YOU ARE HEREBY NOTIFIED that the following shall be added or revised on the Plans and Specifications for the above-referenced project:

1. Delete the April 6, 2015 Section 5-04, HOT MIX ASPHALT Amendment on page 24 and replace it with the following:

SECTION 5-04, HOT MIX ASPHALT

AUGUST 3, 2015

5-04.2 Materials

The third through eighth paragraphs are deleted and replaced with the following:

The Contractor may choose to utilize recycled asphalt pavement (RAP) or reclaimed asphalt shingles (RAS) in the production of HMA. The RAP may be from pavements removed under the Contract, if any, or pavement material from an existing stockpile. The RAS may be from reclaimed shingles.

The Contractor may use up to 20 percent RAP by total weight of HMA with no additional sampling or testing of the RAP. If greater than 20 percent RAP by total weight of HMA or any amount of RAS is utilized in the production of HMA, the Contractor shall sample and test the RAP and RAS during stockpile construction in accordance with WSDOT FOP for AASHTO T 308 for determination of asphalt binder content and WSDOT FOP for WAQTC/AASHTO T 27/T 11 for gradation of the aggregates. The RAP shall be sampled and tested at a frequency of one sample for every 1,000 tons produced and not less than ten samples per project. The RAS shall be sampled and tested at a frequency of one sample for every 100 tons produced and not less than ten samples per project. The asphalt content and gradation test data shall be reported to the Contracting Agency when submitting the mix design for approval on the QPL. If utilized, the amount of RAS shall not exceed 5-percent of the total weight of the HMA. The Contractor shall include the RAP and RAS as part of the mix design as defined in these Specifications.

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

The grade of asphalt binder shall be as required by the Contract. Blending of asphalt binder from different sources is not permitted.

The Contractor may only use warm mix asphalt (WMA) processes in the production of HMA with 20 percent or less RAP by total weight of HMA and no RAS. The Contractor shall submit to the Engineer for approval the process that is proposed and how it will be used in the manufacture of HMA.

When the Contracting Agency provides aggregates or provides a source for the production of aggregates, the Contract Provisions will establish the approximate percentage of asphalt binder required in the mixture for each class of HMA.

Production of aggregates shall comply with the requirements of Section 3-01.

Preparation of stockpile site, the stockpiling of aggregates, and the removal of aggregates from stockpiles shall comply with the requirements of Section 3-02.

5-04.3(1) Hot Mix Asphalt Mixing Plant

In the first paragraph, the last sentence of item number 4 is revised to read:

The Contractor shall provide for the setup and operation of the field testing facilities of the Contracting Agency as provided for in Section 3-01.2(2).

The first paragraph is supplemented with the following:

6. **Equipment for Processing RAP and RAS.** When producing HMA for mix designs with greater than 20 percent RAP by total weight of HMA or any amount of RAS the HMA plant shall be equipped with screens or a lump breaker to eliminate oversize RAP/RAS particles from entering the pug mill or drum mixer.

5-04.3(3)A Material Transfer Device/Vehicle

The first paragraph is supplemented with the following new sentence:

At the Contractor's request the Engineer may approve paving without an MTD/V; the Engineer will determine if an equitable adjustment in cost or time is due.

In the last sentence of the second paragraph, "Project Engineer" is revised to read "Engineer".

5-04.3(5)A Preparation of Existing Surfaces

The first sentence of the last paragraph is revised to read:

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

Unless otherwise approved by the Engineer, the tack coat shall be CSS-1 or CSS-1h emulsified asphalt.

5-04.3(7) Preparation of Aggregates

This section is revised to read:

The aggregates, RAP and RAS shall be stockpiled according to the requirements of Section 3-02. Sufficient storage space shall be provided for each size of aggregate, RAP and RAS. The Contractor may uniformly blend fine aggregate or RAP with the RAS as a method of preventing the agglomeration of RAS particles. The aggregates, RAP and RAS shall be removed from stockpile(s) in a manner to ensure minimal segregation when being moved to the HMA plant for processing into the final mixture. Different aggregate sizes shall be kept separated until they have been delivered to the HMA plant.

5-04.3(7)A1 General

This section is revised to read:

An approved mix design, listed on the Qualified Products List (QPL), is required for all HMA paving. The Contractor shall develop a mix design prior to the initial production of HMA and no more than 3 months prior to submitting for QPL evaluation. The mix design shall be developed in accordance with WSDOT Standard Operating Procedure 732 and meet the requirements of Sections 9-03.8(2) and 9-03.8(6).

Mix designs shall be submitted by the Contractor to the WSDOT State Materials Laboratory on WSDOT Form 350-042EF. If the mix design is approved it will be listed on the QPL for up to 24 consecutive months. Mix designs not listed on the QPL or past the 24 month approved period shall not be used. After a mix design has been on the QPL for 12 months the listing will be extended provided the Contractor submits a certification letter to the Qualified Products Engineer verifying that the aggregate and asphalt binder have not changed. The Contractor may submit the certification one month prior to expiration of the mix design approval. Within 7 calendar days of receipt of the Contractor's certification the QPL will be updated. The maximum duration for approval of a mix design and listing on the QPL will be 24 months from the date of initial approval or as approved by the Engineer.

Changes to the job mix formula of a mix design may require the development of a new mix design and resubmittal for QPL approval.

Changes to aggregate that may require a new mix design include the source of material or a change in the percentage of material from a stockpile greater than 5 percent. Changes to the percentage of material from a stockpile will be

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

calculated exclusive of the RAP content for mix designs with 20 percent RAP or less by total weight of HMA.

Changes to asphalt binder that may require a new mix design include the source of the crude petroleum supplied to the refinery, the refining process, and additives or modifiers in the asphalt binder.

The Contractor shall include the brand and type of anti-stripping additive in the mix design submittal and provide certification from the asphalt binder manufacture that the anti-stripping additive is compatible with the crude source and formulation of asphalt binder proposed in the mix design. All changes to anti-strip require the submittal of a new mix design for approval.

Mix designs with 20 percent RAP or less by total weight of HMA and no RAS will be completed without the inclusion of the RAP. For HMA mix designs with greater than 20 percent RAP by total weight of HMA or any amount of RAS the Contractor shall develop a mix design including RAP, RAS, recycling agent and new asphalt binder. Asphalt binder contributed from RAS shall be determined in accordance with AASHTO PP 78. The total quantity of asphalt binder from the RAP and RAS shall not exceed 40 percent of the total asphalt binder content of the HMA.

Once the RAP and RAS stockpiles have been constructed the Contractor shall extract, recover and test the asphalt residue from the RAP and RAS stockpiles to determine the percent of recycling agent and/or grade of new asphalt binder needed to meet the grade of asphalt binder required by the contract. The asphalt extraction testing shall be performed in accordance with AASHTO T 164 or ASTM D 2172 using reagent grade trichloroethylene. The asphalt recovery shall be performed in accordance with AASHTO R 59 or ASTM D 1856. The recovered asphalt residue shall be tested in accordance with AASHTO R 29 to determine the asphalt binder grade in accordance with Section 9-02.1(4). Once the recovered asphalt binder grade is determined the percent of recycling agent and/or grade of new asphalt binder shall be determined in accordance with ASTM D 4887. The final blend of recycling agent, recovered and new asphalt shall be tested in accordance with AASHTO R 29. The final blended asphalt binder shall be the grade as required by the Contract and comply with the requirements of in accordance with Section 9-02.1(4).

5-04.3(7)A2 Statistical or Nonstatistical Evaluation

This section is revised to read:

The Contractor shall submit WSDOT Form 350-041EF to the Engineer for approval to use a mix design from the QPL. The Contractor may include changes to the job mix formula that have been approved on other contracts. The request

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

to use a mix design from the QPL may be rejected if production of the HMA from another contract is not in compliance with Section 5-04.3(11)D.

The Contractor shall submit representative samples of the materials that are to be used in the HMA production to the State Materials Laboratory in Tumwater. For HMA mix designs with 20 percent RAP or less by total weight of HMA and no RAS, the Contractor shall submit representative samples of the mineral materials that are to be used in the HMA production; the submittal of RAP samples is not required for these mix designs. For HMA mix designs with greater than 20 percent RAP by total weight of HMA or any amount of RAS the Contractor shall submit representative samples of the mineral materials, RAP, RAS and 100 grams of recovered asphalt residue from the RAP and RAS that are to be used in the HMA production. The Contracting Agency will use these samples to evaluate the mix design for approval on the QPL in accordance with WSDOT Standard Practice QC-8.

5-04.3(7)A3 Commercial Evaluation

This section is revised to read:

Approval of a Commercial Evaluation mix design for listing on the QPL will be based on a review of the Contractor's submittal of WSDOT Form 350-042EF for conformance to the requirements of Section 9-03.8(2). Testing of the HMA by the Contracting Agency for mix design approval is not required. Mix designs for HMA with greater than 20 percent RAP by total weight of HMA or any amount of RAS may be evaluated in accordance with Section 5-04.3(7)A2.

For the Bid item Commercial HMA, the Contractor shall select a class of HMA and design level of Equivalent Single Axle Loads (ESAL's) appropriate for the required use.

5-04.3(8) Mixing

The first sentence of the second paragraph is revised to read:

When discharged, the temperature of the HMA shall not exceed the optimum mixing temperature by more than 25°F as shown on the reference mix design report or as approved by the Engineer.

The last paragraph is supplemented with the following new sentence:

After the required amount of mineral materials, RAP, RAS, new asphalt binder and asphalt rejuvenator have been introduced into the mixer the HMA shall be mixed until complete and uniform coating of the particles and thorough distribution of the asphalt binder throughout the mineral materials, RAP and RAS is ensured.

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

5-04.3(8)A4 Definition of Sampling and Sublot

The second sentence of the second paragraph is revised to read:

The sublots shall be approximately uniform in size with a maximum sublot size based on original Plan quantity tons as specified in the following table.

This section is supplemented with the following new table:

HMA Original Plan Quantity (tons)	Sublot Size (tons)
<20,000	1,000
20,000 to 30,000	1,500
>30,000	2,000

5-04.3(8)A7 Test Section – HMA Mixtures

This section is revised to read:

For each class of HMA accepted by statistical evaluation with 20 percent RAP or less by total weight of HMA and no RAS, the Contractor may request a single test section to determine whether the mixture meets the requirements of Section 9-03.8(2) and 9-03.8(6). For each HMA mix design accepted by statistical evaluation with greater than 20 percent RAP by weight of HMA or any amount of RAS, the Contractor shall construct a test section to determine whether the mixture meets the requirements of Sections 9-03.8(2) and 9-03.8(6). Test sections shall be constructed at the beginning of paving and will be at least 600 tons and a maximum of 1,000 tons or as approved by the Engineer. For a test section to be acceptable the pay factor (PF) for gradation, asphalt binder and Va shall be 0.95 or greater for each constituent and the remaining test requirements in Section 9-03.8(2) (fracture, uncompacted void, sand equivalent, dust/asphalt ratio, Hamburg and IDT) shall conform to the requirements of that section. No further wearing or leveling HMA will be paved on any of the four calendar days following construction of the test section. The mixture in the test section will be evaluated as a lot with a minimum of three sublots required. If more than one test section is required, each test section shall be a separate lot.

5-04.3(10)A General

In the first paragraph, “checking” and “cracking” are deleted.

In the third paragraph, the following new sentence is inserted after the second sentence:

Coverage with a steel wheel roller may precede pneumatic tired rolling.

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

In the third paragraph, the following new sentence is inserted before the last sentence:

Regardless of mix temperature, a roller shall not be operated in a mode that results in checking or cracking of the mat.

5-04.3(10)B1 General

In this section, "Project Engineer" is revised to read "Engineer".

The first paragraph is revised to read:

HMA mixture accepted by statistical or nonstatistical evaluation that is used in traffic lanes, including lanes for ramps, truck climbing, weaving, and speed change, and having a specified compacted course thickness greater than 0.10-foot, shall be compacted to a specified level of relative density. The specified level of relative density shall be a Composite Pay Factor (CPF) of not less than 0.75 when evaluated in accordance with Section 1-06.2, using a minimum of 91 percent of the maximum density. The specified level of density attained will be determined by the statistical evaluation of the density of the pavement. The density of the pavement shall be determined in accordance with WSDOT FOP for WAQTC TM 8 when using the nuclear density gauge and WSDOT SOP 736 when using cores to determine density.

The following four new paragraphs are inserted after the first paragraph:

Tests for the determination of the pavement density will be taken in accordance the required procedures for measurement by a nuclear density gauge or roadway cores after completion of the finish rolling.

If the Contracting Agency uses a nuclear density gauge to determine density the test procedures FOP for WAQTC TM 8 and WSDOT SOP T 729 will be used on the day the mix is placed.

Roadway cores for density may be obtained by either the Contracting Agency or the Contractor in accordance with WSDOT SOP 734. The core diameter shall be 4-inches unless otherwise approved by the Engineer. Roadway cores will be tested by the Contracting Agency in accordance with WSDOT FOP for AASHTO T 166.

If the Contract includes the Bid item "Roadway Core" the cores shall be obtained by the Contractor in the presence of the Engineer on the same day the mix is placed and at locations designated by the Engineer. If the Contract does not include the Bid item "Roadway Core" the Contracting Agency will obtain the cores.

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

In the sixth paragraph (after the preceding Amendments are applied), the second sentence is revised to read:

Sublots will be uniform in size with a maximum subplot size based on original Plan quantity tons of HMA as specified in the table below.

The following new table is inserted before the second to last paragraph:

HMA Original Plan Quantity (tons)	Sublot Size (tons)
<20,000	100
20,000 to 30,000	150
>30,000	200

5-04.3(10)B4 Test Results

The first paragraph is revised to read:

The results of all compaction acceptance testing and the CPF of the lot after three sublots have been tested will be available to the Contractor through WSDOT's website. Determination of the relative density of the HMA with a nuclear density gauge requires a correlation factor and may require resolution after the correlation factor is known. When a core is taken for gauge correlation at the location of a subplot, the relative density of the core will be used for the subplot test result and is exempt from retesting. Acceptance of HMA compaction will be based on the statistical evaluation and CPF so determined.

In the second paragraph, the first sentence is revised to read:

For a subplot that has been tested with a nuclear density gauge that did not meet the minimum of 91 percent of the reference maximum density in a compaction lot with a CPF below 1.00 and thus subject to a price reduction or rejection, the Contractor may request that a core be used for determination of the relative density of the subplot.

In the second sentence of the second paragraph, "moisture-density" is revised to read "density".

In the second paragraph, the fourth sentence is deleted.

5-04.3(20) Anti-Stripping Additive

This section is revised to read:

Anti-stripping additive shall be added to the liquid asphalt by the asphalt supplier prior to shipment to the asphalt mixing plant. Anti-stripping additive shall be

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

added in the amount designated on the QPL for the mix design. Anti-strip is not required for temporary work that will be removed prior to Completion.

5-04.4 Measurement

The following new paragraph is inserted after the first paragraph:

Roadway cores will be measured per each for the number of cores taken.

The second to last paragraph is deleted.

5-04.5 Payment

The bid item "Removing Temporary Pavement Marking", per linear foot and paragraph following bid item are deleted.

The following new bid item is inserted before the second to last paragraph:

"Roadway Core", per each.

The Contractor's costs for all other Work associated with the coring (e.g., traffic control) shall be incidental and included within the unit Bid price per each and no additional payments will be made.

2. Replace "2012 edition" in the first sentence of the INTRODUCTION TO THE SPECIAL PROVISIONS on page 24 of the Special Provisions with "2014 edition".

3. Add the following Special Provision:

PAVEMENT REINFORCEMENT GRID

(WC GSP) 5-04

MATERIALS

(WC GSP) 5-04

(WC GSP) 5-04.INST1

Section 5-04 is supplemented with the following:

JUNE 18, 2002 (WC GSP) 5-04

Pavement reinforcement grid shall consist of a fiberglass based grid, coated with an elastomeric polymer, which conforms to the following criteria:

1. Tensile Strength (Test method ASTM D6637-01)

Component Strand Strength	560 lbs./in. min.
Elongation at Break	5 % max.

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210

N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

2. Melting Point (Test method ASTM D 276) 425 F min.
3. Weight (Test method ASTM D5261-92) 11 oz./sq. yd. min.
4. Coated with adhesive backing
5. Minimum Roll Width 5 feet

CONSTRUCTION REQUIREMENTS

(WC GSP) 5-04

(WC GSP) 5-04.INST1

Section 5-04 is supplemented with the following:

JUNE 18, 2002 (WC GSP) 5-04

Prior to placing the grid, the existing pavement surface shall be washed three days prior to installation and broomed the day of installation to the satisfaction of the Engineer, to allow for proper adhesion of the grid.

The grid shall be laid on tack coat, after it has broken and cured to manufacturers recommendations, by mechanical means or by hand under sufficient tension to eliminate ripples.

The surface of the grid shall be rolled with a pneumatic tire roller to activate the adhesive. The tires must be clean to avoid "pick up" of the grid. A vehicle with rubber tires may be used to adhere the reinforcing mesh, if approved by the engineer.

MEASUREMENT

(WC GSP) 5-04

(WC GSP) 5-04.INST1

Section 5-04 is supplemented with the following:

JUNE 18, 2002 (WC GSP) 5-04

Pavement reinforcement grid shall be measured by the square yard for the ground surface area actually covered.

PAYMENT

(WC GSP) 5-04

(WC GSP) 5-04.INST1

Section 5-04 is supplemented with the following:

WHITMAN COUNTY
Department of Public Works

Mailing Address:
P.O. Box 430
Colfax, WA 99111-0430

Administration/Engineering
Road Maintenance
Equipment Rental & Revolving
Solid Waste Division
Planning Division
Building & Development

PHONE: (509) 397-6206
Fax: (509) 397-6210


N. 310 Main
2nd Floor Public Service Bldg.
Colfax, WA 99111

JUNE 18, 2002 (WC GSP) 5-04

"Pavement Reinforcement Grid ", per square yard.

4. The Federal Wage Determination listed in the contract provisions (WA150001, Modification 12) is replaced with the attached copy of WA150001, Modification 13.
5. Delete the "PROPOSAL" Form in its entirety and replace it with the attached "PROPOSAL-Revised 8/24/15" Form. HMA PG 64-22 is revised to HMA PG 64-28.
6. Pages 3, 4, 5 and 8 of the plan sheets are deleted and replaced with the attached Revised Page 3, 4, 5 and 8 Plan Sheets. HMA PG 64-22 is revised to HMA PG 64-28.

Sincerely,


W. Mark Storey, P.E.
Director/County Engineer

EXPIRES 9-22-16

SUMMARY OF ESTIMATED QUANTITIES


ITEM NO.	STD. ITEM NO.	UNIT	ITEM	TOTAL QUANTITY
<i>PREPARATION</i>				
1	0001	L.S.	MOBILIZATION	1
2	0188	L.F.	REMOVING TEMPORARY PAVEMENT MARKING	18,691
<i>SURFACING</i>				
3	5120	TON	CRUSHED SURFACING TOP COURSE	2,310
<i>LIQUID ASPHALT</i>				
4	5296	TON	ASPHALT EMULSION CRS-2P	352
5	5340	TON	ASPHALT FOR FOG SEAL	87
<i>BITUMINOUS SURFACE TREATMENT</i>				
6	5436	TON	FURNISHING AND PLACEING 3/8" CHIPS	2,420
<i>HOT MIX ASPHALT</i>				
7	5717	TON	HMA FOR PRELEVELING CL. 1/2 IN. PG 64-28	2,410
8	5767	TON	HMA CL. 1/2 IN. PG 64-28	4,450
9	5830	CALC	JOB MIX COMPLIANCE PRICE ADJUSTMENT	1
10	5835	CALC	COMPACTION PRICE ADJUSTMENT	1
11		S.Y.	PAVEMENT REINFORCEMENT GRID	19,000
<i>TRAFFIC</i>				
12	6806	L.F.	PAINT LINE	196,954
13	6858	L.F.	PAINTED STOP LINE	90
14	6878	EACH	PAINTED RAILROAD CROSSING SYMBOL	2
15	6895	L.F.	TEMPORARY PAVEMENT MARKING - SHORT DURATION	139,804
16	6971	L.S.	PROJECT TEMPORARY TRAFFIC CONTROL	1
17	6982	S.F.	CONSTRUCTION SIGNS CLASS A	1,498
<i>OTHER ITEMS</i>				
18	7490	L.S.	TRIMMING AND CLEANUP	1
19	7736	L.S.	SPCC PLAN	1

NOTE: FOR SPECIAL FEATURES SEE SPECIAL PROVISIONS.


APPROVED:




EXPIRES 09-22-16



- NOTE:
 1.) OVERLAY AT EXISTING PAVED WIDTH. EXISTING WIDTH VARIES FROM 25' TO 60'.
 2.) MATCH EXISTING SHOULDER WIDTH. EXISTING WIDTH VARIES FROM 2' TO 4'.
 3.) TEMPORARY PAVEMENT MARKING TAPE SHALL BE USED FOR HMA OVERLAY SECTIONS. TEMPORARY PAVEMENT MARKING TAPE SHALL BE REMOVED & REPLACED PRIOR TO FOG SEAL WITH TEMPORARY RAISED PAVEMENT MARKERS.
 4.) 0.20' COMPACTED HMA CL. 1/2 IN. PG 64-28 WITH TACK COAT ON ROSALIA EXIT NORTH RD. AND 0.15' COMPACTED HMA CL. 1/2 IN. PG 64-28 WITH TACK COAT ON ROSALIA RD. BETWEEN M.P. 2.23 & M.P. 2.42.



- NOTE:
 1.) SEAL COAT AT EXISTING PAVED WIDTH. EXISTING WIDTH VARIES FROM 24' TO 28'.
 2.) TEMPORARY RAISED PAVEMENT MARKERS SHALL BE USED FOR SEAL COAT SECTIONS.



- NOTE:
 1.) OVERLAY AT EXISTING PAVED WIDTH. EXISTING WIDTH VARIES FROM 20' TO 28' BETWEEN M.P. 0.49 AND M.P. 0.91 AND BETWEEN M.P. 2.48 AND M.P. 3.67.
 2.) EXACT LOCATIONS OF REINFORCEMENT GRID WILL BE DETERMINED PRIOR TO PLACEMENT.
 3.) PRELEVEL SURFACE SHALL BE SWEEPED ON THE DAY OF PAVING & WASHED 3 DAYS PRIOR TO APPLICATION OF TACK COAT & GRID BY CONTRACTOR.
 4.) MATCH EXISTING SHOULDER WIDTH. EXISTING WIDTH VARIES FROM 2' TO 4'.
 5.) TEMPORARY PAVEMENT MARKING TAPE SHALL BE USED FOR HMA OVERLAY SECTIONS. TEMPORARY PAVEMENT MARKING TAPE SHALL BE REMOVED & REPLACED PRIOR TO FOG SEAL WITH TEMPORARY RAISED PAVEMENT MARKERS.

GENERAL NOTES:


- 1.) ALL DIMENSIONS ARE FEET UNLESS OTHERWISE NOTED.
- 2.) CONTRACTING AGENCY WILL MARK B.O.P., E.O.P., AND TRANSITIONS. CONTRACTOR IS REQUIRED TO GIVE 48 HOURS NOTICE TO START OF ANY WORK ON THE PROJECT.
- 3.) DIRECTION OF PAVING SHALL BE DETERMINED BY THE ENGINEER PRIOR TO PAVING.
- 4.) EXISTING ROAD SURFACE SHALL BE SWEEPED ON THE DAY OF PAVING PRIOR TO APPLICATION OF TACK COAT BY CONTRACTOR.
- 5.) TACK COAT APPLICATION SHALL BE A MINIMUM OF 0.09 GALLONS PER SQUARE YARD. RAPID CURE EMULSIFIED ASPHALT FOG SEAL SHALL BE APPLIED AT 0.08 TO 0.12 GALLONS PER SQUARE YARD.
- 6.) THE CONTRACTOR SHALL PROVIDE TEMPORARY PAVEMENT MARKING DURING CONSTRUCTION, AND SHALL APPLY PAINT STRIPE AFTER COMPLETION OF THE PROJECT.
- 7.) SEAL COAT WORK SHALL BE DONE PRIOR TO HMA OVERLAYS.
- 8.) CLASS B SIGNING AND TEMPORARY TRAFFIC CONTROL DEVICES ARE THE RESPONSIBILITY OF THE CONTRACTOR AND ARE INCIDENTAL TO BID ITEM 16
- 9.) SEE STANDARD PLANS AND THE CURRENT ADDITION OF THE MUTCD FOR SIGN, DEVICE AND BUFFER SPACING.

APPROVED:




EXPIRES 09-22-16

1	8/20	ML	DC	MS	CHANGED PG 64-22 TO PG 64-28	Drawn By: M. LA VANWAY	Date: 05/2015	SCALE HORIZONTAL: AS SHOWN VERTICAL: AS SHOWN	WHITMAN COUNTY ENGINEER 310 N. MAIN ST. COLFAX WA. 99111 (509) 397-6206	PLANS PREPARED UNDER THE DIRECTION OF: MARK STOREY, P.E. COUNTY ENGINEER	COUNTY ROAD PROJECT NO. 0017-2, 0025-3 & 2500-8 GENERAL NOTES & SECTION DETAILS COUNTYWIDE OVERLAYS 3	SHEET 4 OF 12
1	8/20	ML	DC	MS	CHANGED GENERAL NOTE 8	Designed By: M. STOREY	Date: 05/2015					
No.	Date	By	Ckd.	Appr.	Revision	Checked By: M. STOREY	Date: 05/2015					



TYPICAL HMA APPROACH SECTION
N.T.S.




TYPICAL HMA APPROACH
N.T.S.


ROSALIA RD NO. 0017 TABLE OF HMA APPROACHES		
MILEPOST AT CENTERLINE OF APPROACH	TYPE	WIDTH
2.54 RT	PINE CITY-MALDEN CO. RD. APPROACH	125.00'
3.09 LT	WSDOT STOCKPILE SITE APPROACH	230.00'
3.15 LT	WSDOT STOCKPILE SITE APPROACH	140.00'
3.26 LT	WSDOT STOCKPILE SITE APPROACH	100.00'
3.48 RT	FIELD APPROACH	52.00'
3.62 RT	GALE CO. RD. APPROACH	225.00'

ROSALIA EXIT NORTH ROAD NO. 0025 TABLE OF HMA APPROACHES		
MILEPOST AT CENTERLINE OF APPROACH	TYPE	WIDTH
0.00 B.O.P.	ROSALIA CO. RD. APPROACH	245.00'
0.13 E.O.P.	SR 195 APPROACH	85.00'


- NOTE:
- 1.) TYPICAL APPROACH DIMENSIONS WILL BE MODIFIED IN THE FIELD TO MATCH EXISTING CONDITIONS.
 - 2.) NO TRANSITION OR APPROACH WORK WILL BE REQUIRED FOR SEAL COAT ROADS.
 - 3.) GRAVEL APPROACH WORK WILL BE DONE IN CONJUNCTION WITH CSTC SHOULDER WORK. CSTC MATERIAL MAY NOT BE PLACED ON NEW HMA PAVEMENT DURING APPROACH WORK.




TRANSITION SECTIONS B.O.P. & E.O.P.
ROSALIA EXIT NORTH RD. - N.T.S.



TRANSITION SECTIONS (TYP)
ROSALIA RD. - N.T.S.
*SEE SECTION DETAILS FOR MORE INFO



TYPICAL GRAVEL APPROACH
N.T.S.



TYPICAL GRAVEL APPROACH SECTION
N.T.S.

APPROVED:



EXPIRES 09-22-16

1 8/20 ML DC MS CHANGED PG 64-22 TO PG 64-28

Drawn By: M. LA VANWAY
Date: 05/2015
Designed By: M. STOREY
Date: 05/2015
Checked By: M. STOREY
Date: 05/2015

SCALE

HORIZONTAL: AS SHOWN
VERTICAL: AS SHOWN

WHITMAN COUNTY ENGINEER

310 N. MAIN ST.
COLFAX WA. 99111
(509) 397-6206

PLANS PREPARED UNDER THE DIRECTION OF:

MARK STOREY, P.E.
COUNTY ENGINEER

Date: 05/2015

COUNTY ROAD PROJECT NO. 0017-2, 0025-3 & 2500-8
APPROACH DETAILS & TRANSITION SECTIONS
COUNTYWIDE OVERLAYS 3














SHEET

5 OF 12

PORTABLE SIGNS & TRAFFIC CONTROL DEVICES

BE PREPARED TO STOP
FLAGMAN AHEAD
ROUGH ROAD
ONE LANE AHEAD
ABRUPT LANE EDGE
SPEED ADVISORY
LOOSE GRAVEL
BUMP
DIP
TRUCK CROSSING
ROAD MACHINERY AHEAD
SHOULDER WORK
PAVEMENT ENDS
EXPECT DELAYS
WAIT FOR PILOT CAR
TYPE 1 BARRICADES AND LIGHTS
CONES
DETOUR ARROWS

INTERSECTION SERIES TO BE PLACED
AT ALL INTERNAL PUBLIC ROAD
INTERSECTIONS ON DRY CREEK RD
EXCEPT PFAFF RD & S PFAFF RD



PLACE SIGNS 12 & 13 IN
EACH TRAVEL DIRECTION



CONSTRUCTION SIGN PLAN

NOTES:

- SEE STANDARD PLANS AND THE CURRENT ADDITION OF THE MUTCD FOR SIGN, DEVICE AND BUFFER SPACING.
- PORTABLE SIGNS AND TRAFFIC CONTROL DEVICES LISTED ARE NOT INTENDED TO BE COMPLETE. OTHER SIGNS MAY BE REQUIRED WITHIN THE PROJECT LIMITS TO ACCOMMODATE CONTRACTOR'S WORK METHODS.
- WHEN PILOT CAR IS IN USE THE "WAIT FOR PILOT CAR" SIGN SHALL BE USED IN PLACE OF A FLAGMAN AT INTERSECTING ROADS.
- CONSTRUCTION SPEED LIMIT WILL BE POSTED AND ENFORCED AT 35 M.P.H.
- CLASS B SIGNING AND TEMPORARY TRAFFIC CONTROL DEVICES ARE THE RESPONSIBILITY OF THE CONTRACTOR AND ARE INCIDENTAL TO BID ITEM 16
- SEE STANDARD PLANS AND THE CURRENT ADDITION OF THE MUTCD FOR SIGN, DEVICE AND BUFFER SPACING.

WB - INDICATES THAT THE SIGN COLORS ARE WHITE AND BLACK
OB - INDICATES THAT THE SIGN COLORS ARE ORANGE AND BLACK

APPROVED:



EXPIRES 09-22-16

No.	Date	By	Ckd.	Appr.	Revision
1	8/20	ML	DC	MS	CHANGED CONSTRUCTION SIGN PLAN NOTE 5

Drawn By: M. LA VANWAY	Date: 05/2015
Designed By: M. STOREY	Date: 05/2015
Checked By: M. STOREY	Date: 05/2015

SCALE
HORIZONTAL: AS SHOWN
VERTICAL: AS SHOWN

PLANS PREPARED UNDER THE
DIRECTION OF:
MARK STOREY, P.E.
COUNTY ENGINEER
Date: 05/2015

COUNTY ROAD PROJECT NO. 0017-2, 0025-3 & 2500-8
CONSTRUCTION SIGNS
COUNTYWIDE OVERLAYS 3

SHEET
8 OF 12

General Decision Number: WA150001 08/21/2015 WA1

Superseded General Decision Number: WA20140001

State: Washington

Construction Type: Highway

Counties: Washington Statewide.

HIGHWAY (Excludes D.O.E. Hanford Site in Benton and Franklin Counties)

Note: Executive Order (EO) 13658 establishes an hourly minimum wage of \$10.10 for 2015 that applies to all contracts subject to the Davis-Bacon Act for which the solicitation is issued on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.10 (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract. The EO minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date	Modification Number	Publication Date
0	01/02/2015	11	07/24/2015
1	01/09/2015	12	07/31/2015
2	01/23/2015	13	08/21/2015
3	02/27/2015		
4	03/20/2015		
5	04/03/2015		
6	05/22/2015		
7	05/29/2015		
8	06/12/2015		
9	07/03/2015		
10	07/10/2015		

CARP0001-008 06/01/2015

Rates Fringes

CARPENTER		
GROUP 1	\$ 27.61	14.00
GROUP 2	\$ 41.86	14.49
GROUP 3	\$ 32.97	14.00
GROUP 4	\$ 31.94	14.00
GROUP 5	\$ 73.44	14.00
GROUP 6	\$ 35.02	14.00
GROUP 7	\$ 36.72	14.00
GROUP 8	\$ 33.27	14.00
GROUP 9	\$ 35.02	14.00

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

CARPENTER & DIVER CLASSIFICATIONS:

- GROUP 1: Carpenter
- GROUP 2: Millwright, machine erector
- GROUP 3: Piledriver - includes driving, pulling, cutting, placing collars, setting, welding, or creosote treated material, on all piling
- GROUP 4: Bridge carpenters
- GROUP 5: Diver Wet
- GROUP 6: Diver Tender, Manifold Operator, ROV Operator
- GROUP 7: Diver Standby, Bell/Vehicle or Submersible operator Not Under Pressure
- GROUP 8: Assistant Tender, ROV Tender/Technician
- GROUP 9: Manifold Operator-Mixed Gas

ZONE PAY:

ZONE 1	0-40 MILES	FREE
ZONE 2	41-65 MILES	\$2.25/PER HOUR
ZONE 3	66-100 MILES	\$3.25/PER HOUR
ZONE 4	OVER 100 MILES	\$4.75/PER HOUR

DISPATCH POINTS:

CARPENTERS/MILLWRIGHTS: PASCO (515 N Neel Street) or Main Post Office of established residence of employee (Whichever is closest to the worksite).

CARPENTERS/PILEDRIIVER: SPOKANE (127 E. AUGUSTA AVE.) or Main Post Office of established residence of employee (Whichever is closest to the worksite).

CARPENTERS: WENATCHEE (27 N. CHELAN) or Main Post Office of established residence of employee (Whichever is closest to the worksite).

CARPENTERS: COEUR D' ALENE (1839 N. GOVERNMENT WAY) or Main Post Office of established residence of employee (Whichever is closest to the worksite).

CARPENTERS: MOSCOW (302 N. JACKSON) or Main Post Office of established residence of employee (Whichever is closest to the worksite).

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

DEPTH PAY FOR DIVERS BELOW WATER SURFACE:

50-100 feet \$2.00 per foot
101-150 feet \$3.00 per foot
151-220 feet \$4.00 per foot
221 feet and deeper \$5.00 per foot

PREMIUM PAY FOR DIVING IN ENCLOSURES WITH NO VERTICAL ASCENT:

0-25 feet Free
26-300 feet \$1.00 per Foot

SATURATION DIVING:

The standby rate applies until saturation starts. The saturation diving rate applies when divers are under pressure continuously until work task and decompression are complete. the diver rate shall be paid for all saturation hours.

WORK IN COMBINATION OF CLASSIFICATIONS:

Employees working in any combination of classifications within the diving crew (except dive supervisor) in a shift are paid in the classification with the highest rate for that shift.

HAZMAT PROJECTS:

Anyone working on a HAZMAT job (task), where HAZMAT certification is required, shall be compensated at a premium, in addition to the classification working in as follows:

LEVEL D + \$.25 per hour - This is the lowest level of protection. No respirator is used and skin protection is minimal.

LEVEL C + \$.50 per hour - This level uses an air purifying respirator or additional protective clothing.

LEVEL B + \$.75 per hour - Uses same respirator protection as Level A. Supplied air line is provided in conjunction with a chemical "splash suit".

LEVEL A +\$1.00 per hour - This level utilizes a fully encapsulated suit with a self-contained breathing apparatus or a supplied air line.

CARP0003-006 10/01/2011

SOUTHWEST WASHINGTON: CLARK, COWLITZ, KLICKITAT, LEWIS(Piledriver only), PACIFIC (South of a straight line made by extending the north boundary line of Wahkiakum County west to Willapa Bay to the Pacific Ocean), SKAMANIA AND WAHAKIUM COUNTIES and INCLUDES THE ENTIRE PENINSULA WEST OF WILLAPA BAY

SEE ZONE DESCRIPTION FOR CITIES BASE POINTS

ZONE 1:

Table with 3 columns: Job Title, Rates, Fringes. Includes Carpenters, Divers Tenders, Divers, Drywall, Millwrights, Piledrivers.

DEPTH PAY:

50 TO 100 FEET \$1.00 PER FOOT OVER 50 FEET
101 TO 150 FEET \$1.50 PER FOOT OVER 101 FEET
151 TO 200 FEET \$2.00 PER FOOT OVER 151 FEET

Zone Differential (Add up Zone 1 rates):

Zone 2 - \$0.85
Zone 3 - 1.25
Zone 4 - 1.70
Zone 5 - 2.00
Zone 6 - 3.00

BASEPOINTS: ASTORIA, LONGVIEW, PORTLAND, THE DALLES, AND VANCOUVER, (NOTE: All dispatches for Washington State Counties: Cowlitz, Wahkiakum and Pacific shall be from Longview Local #1707 and mileage shall be computed from that point.)

- ZONE 1: Projects located within 30 miles of the respective city hall of the above mentioned cities
ZONE 2: Projects located more than 30 miles and less than 40 miles of the respective city of the above mentioned cities
ZONE 3: Projects located more than 40 miles and less than 50 miles of the respective city of the above mentioned cities
ZONE 4: Projects located more than 50 miles and less than 60 miles of the respective city of the above mentioned cities.
ZONE 5: Projects located more than 60 miles and less than 70 miles of the respective city of the above mentioned cities
ZONE 6: Projects located more than 70 miles of the respected city of the above mentioned cities

CARP0770-003 06/01/2015

	Rates	Fringes
CARPENTER		
CENTRAL WASHINGTON:		
CHELAN, DOUGLAS (WEST OF THE 120TH MERIDIAN), KITTITAS, OKANOGAN (WEST OF THE 120TH MERIDIAN) AND YAKIMA COUNTIES		
CARPENTERS ON CREOSOTE		
MATERIAL.....	\$ 40.46	13.66
CARPENTERS.....	\$ 40.36	13.66
DIVERS TENDER.....	\$ 35.02	14.00
DIVERS.....	\$ 73.44	14.00
MILLWRIGHT AND MACHINE		
ERECTORS.....	\$ 41.86	13.66
PILEDRIIVER, DRIVING, PULLING, CUTTING, PLACING COLLARS, SETTING, WELDING OR CRESOTE TREATED		
MATERIAL, ALL PILING.....	\$ 40.61	13.66

(HOURLY ZONE PAY: WESTERN AND CENTRAL WASHINGTON - ALL CLASSIFICATIONS EXCEPT MILLWRIGHTS AND PILEDRIIVERS)

Hourly Zone Pay shall be paid on jobs located outside of the free zone computed from the city center of the following listed cities:

Seattle	Olympia	Bellingham
Auburn	Bremerton	Anacortes
Renton	Shelton	Yakima
Aberdeen-Hoquiam	Tacoma	Wenatchee
Ellensburg	Everett	Port Angeles
Centralia	Mount Vernon	Sunnyside
Chelan	Pt. Townsend	

Zone Pay:

0 -25 radius miles	Free
26-35 radius miles	\$1.00/hour
36-45 radius miles	\$1.15/hour
46-55 radius miles	\$1.35/hour
Over 55 radius miles	\$1.55/hour

(HOURLY ZONE PAY: WESTERN AND CENTRAL WASHINGTON - MILLWRIGHT AND PILEDRIIVER ONLY)

Hourly Zone Pay shall be computed from Seattle Union Hall, Tacoma City center, and Everett City center

Zone Pay:

0 -25 radius miles	Free
26-45 radius miles	\$.70/hour
Over 45 radius miles	\$1.50/hour

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

CARP0770-006 06/01/2015

	Rates	Fringes
CARPENTER		
WESTERN WASHINGTON:		
CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS (excludes piledrivers only), MASON, PACIFIC (North of a straight line made by extending the north boundary line of Wahkiakum County west to the Pacific Ocean), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES		
BRIDGE CARPENTERS.....	\$ 40.36	13.66
CARPENTERS ON CREOSOTE		
MATERIAL.....	\$ 40.46	13.66
CARPENTERS.....	\$ 40.36	13.66
DIVERS TENDER.....	\$ 44.67	13.66
DIVERS.....	\$ 93.56	13.66
MILLWRIGHT AND MACHINE		
ERECTORS.....	\$ 41.86	13.66
PILEDRIIVER, DRIVING, PULLING, CUTTING, PLACING COLLARS, SETTING, WELDING OR CRESOTE TREATED		
MATERIAL, ALL PILING.....	\$ 40.61	13.66

(HOURLY ZONE PAY: WESTERN AND CENTRAL WASHINGTON - ALL CLASSIFICATIONS EXCEPT MILLWRIGHTS AND PILEDRIIVERS)

Hourly Zone Pay shall be paid on jobs located outside of the free zone computed from the city center of the following listed cities:

Seattle	Olympia	Bellingham
Auburn	Bremerton	Anacortes
Renton	Shelton	Yakima
Aberdeen-Hoquiam	Tacoma	Wenatchee
Ellensburg	Everett	Port Angeles
Centralia	Mount Vernon	Sunnyside
Chelan	Pt. Townsend	

Zone Pay:

0 -25 radius miles	Free
26-35 radius miles	\$1.00/hour
36-45 radius miles	\$1.15/hour
46-55 radius miles	\$1.35/hour
Over 55 radius miles	\$1.55/hour

(HOURLY ZONE PAY: WESTERN AND CENTRAL WASHINGTON - MILLWRIGHT AND PILEDRIIVER ONLY)

Hourly Zone Pay shall be computed from Seattle Union Hall, Tacoma City center, and Everett City center

Zone Pay:

0 -25 radius miles	Free
26-45 radius miles	\$.70/hour
Over 45 radius miles	\$1.50/hour

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

 ELEC0046-001 02/04/2013

CALLAM, JEFFERSON, KING AND KITSAP COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 46.87	3%+15.96
ELECTRICIAN.....	\$ 42.61	3%+15.96

* ELEC0048-003 01/01/2015

CLARK, KLICKITAT AND SKAMANIA COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 44.22	21.50
ELECTRICIAN.....	\$ 40.20	21.50

HOURLY ZONE PAY:

Hourly Zone Pay shall be paid on jobs located outside of the free zone computed from the city center of the following listed cities:

Portland, The Dalles, Hood River, Tillamook, Seaside and Astoria

Zone Pay:

- Zone 1: 31-50 miles \$1.50/hour
- Zone 2: 51-70 miles \$3.50/hour
- Zone 3: 71-90 miles \$5.50/hour
- Zone 4: Beyond 90 miles \$9.00/hour

*These are not miles driven. Zones are based on Delorrne Street Atlas USA 2006 plus.

 ELEC0048-029 01/01/2015

COWLITZ AND WAHIAKUM COUNTY

	Rates	Fringes
CABLE SPLICER.....	\$ 44.22	21.50
ELECTRICIAN.....	\$ 40.20	21.50

ELEC0073-001 07/01/2015

ADAMS, FERRY, LINCOLN, PEND OREILLE, SPOKANE, STEVENS, WHITMAN COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 34.10	16.68
ELECTRICIAN.....	\$ 31.00	16.68

 ELEC0076-002 09/01/2014

GRAYS HARBOR, LEWIS, MASON, PACIFIC, PIERCE, AND THURSTON COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 37.94	23.36
ELECTRICIAN.....	\$ 34.49	23.36

 ELEC0112-005 06/01/2015

ASOTIN, BENTON, COLUMBIA, FRANKLIN, GARFIELD, KITTITAS, WALLA WALLA, YAKIMA COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 40.74	18.65
ELECTRICIAN.....	\$ 38.80	18.59

 ELEC0191-003 06/01/2014

ISLAND, SAN JUAN, SNOHOMISH, SKAGIT AND WHATCOM COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 44.23	17.73
ELECTRICIAN.....	\$ 40.21	17.73

 ELEC0191-004 06/01/2014

CHELAN, DOUGLAS, GRANT AND OKANOGAN COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 40.82	17.63
ELECTRICIAN.....	\$ 37.11	17.63

ENGI0302-003 06/01/2014

CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, KITTITAS, MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, SKAGIT, SNOHOMISH, WHATCOM AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES

PROJECTS: CATEGORY A PROJECTS (EXCLUDES CATEGORY B PROJECTS, AS SHOWN BELOW)

Zone 1 (0-25 radius miles):

	Rates	Fringes
Power equipment operators:		
Group 1A.....	\$ 38.39	17.39
Group 1AA.....	\$ 38.96	17.39
Group 1AAA.....	\$ 39.52	17.39
Group 1.....	\$ 37.84	17.39
Group 2.....	\$ 37.35	17.39
Group 3.....	\$ 36.93	17.39
Group 4.....	\$ 34.57	17.39

Zone Differential (Add to Zone 1 rates):

Zone 2 (26-45 radius miles) - \$1.00

Zone 3 (Over 45 radius miles) - \$1.30

BASEPOINTS: Aberdeen, Bellingham, Bremerton, Everett, Kent, Mount Vernon, Port Angeles, Port Townsend, Seattle, Shelton, Wenatchee, Yakima

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1AAA - Cranes-over 300 tons, or 300 ft of boom (including jib with attachments)

GROUP 1AA - Cranes 200 to 300 tons, or 250 ft of boom (including jib with attachments); Tower crane over 175 ft in height, base to boom

GROUP 1A - Cranes, 100 tons thru 199 tons, or 150 ft of boom (including jib with attachments); Crane-overhead, bridge type, 100 tons and over; Tower crane up to 175 ft in height base to boom; Loaders-overhead, 8 yards and over; Shovels, excavator, backhoes-6 yards and over with attachments

GROUP 1 - Cableway; Cranes 45 tons thru 99 tons, under 150 ft of boom (including jib with attachments); Crane-overhead, bridge type, 45 tons thru 99 tons; Derricks on building work; Excavator, shovel, backhoes over 3 yards and under 6 yards; Hard tail end dump articulating off-road equipment 45 yards and over; Loader- overhead 6 yards to, but not including 8 yards; Mucking machine, mole, tunnel, drill and/or shield; Quad 9, HD 41, D-10; Remote control operator on rubber tired earth moving equipment; Rollagon; Scrapers-self propelled 45 yards and over; Slipform pavers; Transporters, all truck or track type

GROUP 2 - Barrier machine (zipper); Batch Plant Operaor-Concrete; Bump Cutter; Cranes, 20 tons thru 44 tons with attachments; Crane-overhead, bridge type-20 tons through 44 tons; Chipper; Concrete Pump-truck mount with boom attachment; Crusher; Deck Engineer/Deck Winches (power); Drilling machine; Excavator, shovel, backhoe-3yards and under; Finishing Machine, Bidwell, Gamaco and similar equipment; Guardrail punch; Horizontal/directional drill operator; Loaders-overhead under 6 yards; Loaders-plant feed; Locomotives-all; Mechanics-all; Mixers-asphalt plant; Motor patrol graders-finishing; Piledriver (other than crane mount); Roto-mill,roto-grinder; Screedman, spreader, topside operator-Blaw Knox, Cedar Rapids, Jaeger, Caterpillar, Barbar Green; Scraper-self propelled, hard tail end dump, articulating off-road equipment-under 45 yards; Subgrade trimmer; Tractors, backhoes-over 75 hp; Transfer material service machine-shuttle buggy, blaw knox-roadtec; Truck crane oiler/driver-100 tons and over; Truck Mount portable conveyor; Yo Yo Pay dozer

GROUP 3 - Conveyors; Cranes-thru 19 tons with attachments; A-frame crane over 10 tons; Drill oilers-auger type, truck or crane mount; Dozers-D-9 and under; Forklift-3000 lbs. and over with attachments; Horizontal/directional drill locator; Outside hoists-(elevators and manlifts), air tuggers, strato tower bucket elevators; Hydralifts/boom trucks over 10 tons; Loader-elevating type, belt; Motor patrol grader-nonfinishing; Plant oiler- asphalt, crusher; Pumps-concrete; Roller, plant mix or multi-lift materials; Saws-concrete; Scrpers-concrete and carry-all; Service engineer-equipment; Trenching machines; Truck Crane Oiler/Driver under 100 tons; Tractors, backhoe 75 hp and under

GROUP 4 - Assistant Engineer; Bobcat; Brooms; Compressor; Concrete finish mahine-laser screed; Cranes-A frame-10 tons and under; Elevator and Manlift-permanent or shaft type; Gradechecker, Stakehop; Forklifts under 3000 lbs. with attachments; Hydralifts/boom trucks, 10 tons and under; Oil distributors, blower distribution and mulch seeding operator; Pavement breaker; Posthole digger, mechanical; Power plant; Pumps, water; Rigger and Bellman; Roller-other than plant mix; Wheel Tractors, farmall type; Shotcrete/gunite equipment operator

Category B Projects: 95% of the basic hourly reate for each group plus full fringe benefits applicable to category A projects shall apply to the following projects. A Reduced rates may be paid on the following:

1. Projects involving work on structures such as buildings and bridges whose total value is less than \$1.5 million excluding mechanical, electrical, and utility portions of the contract.
2. Projects of less than \$1 million where no building is involved. Surfacing and paving included, but utilities excluded.
3. Marine projects (docks, wharfs, etc.) less than \$150,000.

HANDLING OF HAZARDOUS WASTE MATERIALS:

Personnel in all craft classifications subject to working inside a federally designated hazardous perimeter shall be elgible for compensation in accordance with the following group schedule relative to the level of hazardous waste as outlined in the specific hazardous waste project site safety plan.

H-1 Base wage rate when on a hazardous waste site when not outfitted with protective clothing

H-2 Class "C" Suit - Base wage rate plus \$.25 per hour.

H-3 Class "B" Suit - Base wage rate plus \$.50 per hour.

H-4 Class "A" Suit - Base wage rate plus \$.75 per hour.

Zone Differential (Add to Zone 1 rates):

Zone 2 (26-45 radius miles) - \$.70

Zone 3 (Over 45 radius miles) - \$1.00

BASEPOINTS: Aberdeen, Bellingham, Bremerton, Everett, Kent, Mount Vernon, Port Angeles, Port Townsend, Seattle, Shelton, Wenatchee, Yakima

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1AAA - Cranes-over 300 tons, or 300 ft of boom (including jib with attachments)

GROUP 1AA - Cranes 200 to 300 tons, or 250 ft of boom (including jib with attachments); Tower crane over 175 ft in height, base to boom

GROUP 1A - Cranes, 100 tons thru 199 tons, or 150 ft of boom (including jib with attachments); Crane-overhead, bridge type, 100 tons and over; Tower crane up to 175 ft in height base to boom; Loaders-overhead, 8 yards and over; Shovels, excavator, backhoes-6 yards and over with attachments

GROUP 1 - Cableway; Cranes 45 tons thru 99 tons, under 150 ft of boom (including jib with attachments); Crane-overhead, bridge type, 45 tons thru 99 tons; Derricks on building work; Excavator, shovel, backhoes over 3 yards and under 6 yards; Hard tail end dump articulating off-road equipment 45 yards and over; Loader- overhead 6 yards to, but not including 8 yards; Mucking machine, mole, tunnel, drill and/or shield; Quad 9, HD 41, D-10; Remote control operator on rubber tired earth moving equipment; Rollagon; Scrapers-self propelled 45 yards and over; Slipform pavers; Transporters, all truck or track type

GROUP 2 - Barrier machine (zipper); Batch Plant Operaor- Concrete; Bump Cutter; Cranes, 20 tons thru 44 tons with attachments; Crane-overhead, bridge type-20 tons through 44 tons; Chipper; Concrete Pump-truck mount with boom attachment; Crusher; Deck Engineer/Deck Winches (power); Drilling machine; Excavator, shovel, backhoe-3 yards and under; Finishing Machine, Bidwell, Gamaco and similar equipment; Guardrail punch; Horizontal/directional drill operator; Loaders-overhead under 6 yards; Loaders-plant feed; Locomotives-all; Mechanics-all; Mixers-asphalt plant; Motor patrol graders-finishing; Piledriver (other than crane mount); Roto-mill, roto-grinder; Screedman, spreader, topside operator-Blaw Knox, Cedar Rapids, Jaeger, Caterpillar, Barbar Green; Scraper-self propelled, hard tail end dump, articulating off-road equipment-under 45 yards; Subgrade trimmer; Tractors, backhoes-over 75 hp; Transfer material service machine-shuttle buggy, blaw knox-roadtec; Truck crane oiler/driver-100 tons and over; Truck Mount portable conveyor; Yo Yo Pay dozer

GROUP 3 - Conveyors; Cranes-thru 19 tons with attachments; A-frame crane over 10 tons; Drill oilers-auger type, truck or crane mount; Dozers-D-9 and under; Forklift-3000 lbs. and over with attachments; Horizontal/directional drill locator; Outside hoists-(elevators and manlifts), air tuggers, strato tower bucket elevators; Hydralifts/boom trucks over 10 tons; Loader-elevating type, belt; Motor patrol grader-nonfinishing; Plant oiler- asphalt, crusher; Pumps-concrete; Roller, plant mix or multi-lift materials; Saws-concrete; Scrpers-concrete and carry-all; Service engineer-equipment; Trenching machines; Truck Crane Oiler/Driver under 100 tons; Tractors, backhoe 75 hp and under

GROUP 4 - Assistant Engineer; Bobcat; Brooms; Compressor; Concrete finish mahine-laser screed; Cranes-A frame-10 tons and under; Elevator and Manlift-permanent or shaft type; Gradechecker, Stakehop; Forklifts under 3000 lbs. with attachments; Hydralifts/boom trucks, 10 tons and under; Oil distributors, blower distribution and mulch seeding operator; Pavement breaker; Posthole digger, mechanical; Power plant; Pumps, water; Rigger and Bellman; Roller-other than plant mix; Wheel Tractors, farmall type; Shotcrete/gunite equipment operator

CATEGORY B PROJECTS: 95% OF THE BASIC HOURLY RATE FOR EACH GROUP PLUS FULL FRINGE BENEFITS APPLICABLE TO CATEGORY A PROJECTS SHALL APPLY TO THE FOLLOWING PROJECTS. REDUCED RATES MAY BE PAID ON THE FOLLOWING:

1. Projects involving work on structures such as buildings and bridges whose total value is less than \$1.5 million excluding mechanical, electrical, and utility portions of the contract.
2. Projects of less than \$1 million where no building is involved. Surfacing and paving including, but utilities excluded.
3. Marine projects (docks, wharfs, ect.) less than \$150,000.

HANDLING OF HAZARDOUS WASTE MATERIALS: Personnel in all craft classifications subject to working inside a federally designed hazardous perimeter shall be elgible for compensation in accordance with the following group schedule relative to the level of hazardous waste as outlined in the specific hazardous waste project site safety plan.

- H-1 Base wage rate when on a hazardous waste site when not outfitted with protective clothing.
- H-2 Class "C" Suit - Base wage rate plus \$.25 per hour.
- H-3 Class "B" Suit - Base wage rate plus \$.50 per hour.
- H-4 Class "A" Suit - Base wage rate plus \$.75 per hour.

ENGI0370-002 06/01/2015

ADAMS, ASOTIN, BENTON, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, FRANKLIN, GARFIELD, GRANT, LINCOLN, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES

ZONE 1:

	Rates	Fringes
POWER EQUIPMENT OPERATOR		
GROUP 1.....	\$ 26.16	13.55
GROUP 2.....	\$ 26.48	13.55
GROUP 3.....	\$ 27.09	13.55
GROUP 4.....	\$ 27.25	13.55
GROUP 5.....	\$ 27.41	13.55
GROUP 6.....	\$ 27.69	13.55
GROUP 7.....	\$ 27.96	13.55
GROUP 8.....	\$ 29.06	13.55

ZONE DIFFERENTIAL (Add to Zone 1 rate): Zone 2 - \$2.00

Zone 1: Within 45 mile radius of Spokane, Pasco, Washington; Lewiston, Idaho

Zone 2: Outside 45 mile radius of Spokane, Pasco, Washington; Lewiston, Idaho

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Bit Grinders; Bolt Threading Machine; Compressors (under 2000 CFM, gas, diesel, or electric power); Deck Hand; Fireman & Heater Tender; Hydro-seeder, Mulcher, Nozzleman; Oiler Driver, & Cable Tender, Mucking Machine; Pumpman; Rollers, all types on subgrade, including seal and chip coatings (farm type, Case, John Deere & similar, or Compacting Vibrator), except when pulled by Dozer with operable blade; Welding Machine; Crane Oiler-Driver (CLD required) & Cable Tender, Mucking Machine

GROUP 2: A-frame Truck (single drum); Assistant Refrigeration Plant (under 1000 ton); Assistant Plant Operator, Fireman or Pugmixer (asphalt); Bagley or Stationary Scraper; Belt Finishing Machine; Blower Operator (cement); Cement Hog; Compressor (2000 CFM or over, 2 or more, gas diesel or electric power); Concrete Saw (multiple cut); Distributor Leverman; Ditch Witch or similar; Elevator Hoisting Materials; Dope Pots (power agitated); Fork Lift or Lumber Stacker, hydra-lift & similar; Gin Trucks (pipeline); Hoist, single drum; Loaders (bucket elevators and conveyors); Longitudinal Float; Mixer (portable-concrete); Pavement Breaker, Hydra-Hammer & similar; Power Broom; Railroad Ballast Regulation Operator (self-propelled); Railroad Power Tamper Operator (self-propelled); Railroad Tamping Jack Operator (self-propelled); Spray Curing Machine (concrete); Spreader Box (self-propelled); Straddle Buggy (Ross & similar on construction job only); Tractor (Farm type R/T with attachment, except Backhoe); Tugger Operator

GROUP 3: A-frame Truck (2 or more drums); Assistant Refrigeration Plant & Chiller Operator (over 1000 ton); Backfillers (Cleveland & similar); Batch Plant & Wet Mix Operator, single unit (concrete); Belt-Crete Conveyors with power pack or similar; Belt Loader (Kocal or similar); Bending Machine; Bob Cat (Skid Steer); Boring Machine (earth); Boring Machine (rock under 8 inch bit) (Quarry Master, Joy or similar); Bump Cutter (Wayne, Saginaw or similar); Canal Lining Machine (concrete); Chipper (without crane); Cleaning & Doping Machine (pipeline); Deck Engineer; Elevating Belt-type Loader (Euclid, Barber Green & similar); Elevating Grader-type Loader (Dumor, Adams or similar); Generator Plant Engineers (diesel or electric); Gunnite Combination Mixer & Compressor; Locomotive Engineer; Mixermobile; Mucking Machine; Posthole Auger or Punch; Pump (grout or jet); Soil Stabilizer (P & H or similar); Spreader Machine; Dozer/Tractor (up to D-6 or equivalent) and Traxcavator; Traverse Finish Machine; Turnhead Operator

GROUP 4: Concrete Pumps (squeeze-crete, flow-crete, pump-crete, Whitman & similar); Curb Extruder (asphalt or concrete); Drills (churn, core, calyx or diamond); Equipment Serviceman; Greaser & Oiler; Hoist (2 or more drums or Tower Hoist); Loaders (overhead & front-end, under 4 yds. R/T); Refrigeration Plant Engineer (under 1000 ton); Rubber-tired Skidders (R/T with or without attachments); Surface Heater & Plant Machine; Trenching Machines (under 7 ft. depth capacity); Turnhead (with re-screening); Vacuum Drill (reverse circulation drill under 8 inch bit)

GROUP 5: Backhoe (under 45,000 gw); Backhoe & Hoe Ram (under 3/4 yd.); Carrydeck & Boom Truck (under 25 tons); Cranes (25 tons & under), all attachments including clamshell, dragline; Derricks & Stifflegs (under 65 tons); Drilling Equipment (8 inch bit & over) (Robbins, reverse circulation & similar); Hoe Ram; Piledriving Engineers; Paving (dual drum); Railroad Track Liner Operatr (self-propelled); Refrigeration Plant Engineer (1000 tons & over); Signalmen (Whirleys, Highline Hammerheads or similar); Grade Checker

GROUP 6: Asphalt Plant Operator; Automatic Subgrader (Ditches & Trimmers)(Autograde, ABC, R.A. Hansen & similar on grade wire); Backhoe (45,000 gw and over to 110,000 gw); Backhoes & Hoe Ram (3/4 yd. to 3 yd.); Batch Plant (over 4 units); Batch & Wet Mix Operator (multiple units, 2 & incl. 4); Blade Operator (motor patrol & attachments); Cable Controller (dispatcher); Compactor (self-propelled with blade); Concrete Pump Boom Truck; Concrete Slip Form Paver; Cranes (over 25 tons, to and including 45 tons), all attachments including clamshell, dragline; Crusher, Grizzle & Screening Plant Operator; Dozer, 834 R/T & similar; Drill Doctor; Loader Operator (front-end & overhead, 4 yds. incl. 8 yds.); Multiple Dozer Units with single blade; Paving Machine (asphalt and concrete); Quad-Track or similar equipment; Rollerman (finishing asphalt pavement); Roto Mill (pavement grinder); Scrapers, all, rubber-tired; Screed Operator; Shovel (under 3 yds.); Trenching Machines (7 ft. depth & over); Tug Boat Operator Vactor guzzler, super sucker; Lime Batch Tank Operator (REcycle Train); Lime Brain Operator (Recycle Train); Mobile Crusher Operator (Recycle Train)

GROUP 7: Backhoe (over 110,000 gw); Backhoes & Hoe Ram (3 yds & over); Blade (finish & bluetop) Automatic, CMI, ABC, Finish Athey & Huber & similar when used as automatic; Cableway Operators; Concrete Cleaning/Decontamination machine operator; Cranes (over 45 tons to but not including 85 tons), all attachments including clamshell and dragline; Derricks & Stiffleys (65 tons & over); Elevating Belt (Holland type); Heavy equipment robotics operator; Loader (360 degrees revolving Koehring Scooper or similar); Loaders (overhead & front-end, over 8 yds. to 10 yds.); Rubber-tired Scrapers (multiple engine with three or more scrapers); Shovels (3 yds. & over); Whirleys & Hammerheads, ALL; H.D. Mechanic; H.D. Welder; Hydraulic Platform Trailers (Goldhofer, Shaurerly and Similar); Ultra High Pressure Waterjet Cutting Tool System Operator (30,000 psi); Vacuum Blasting Machine Operator

GROUP 8: Cranes (85 tons and over, and all climbing, overhead, rail and tower), all attachments including clamshell, dragline; Loaders (overhead and front-end, 10 yards and over); Helicopter Pilot

BOOM PAY: (All Cranes, Including Tower)
 180 ft to 250 ft \$.50 over scale
 Over 250 ft \$.80 over scale

NOTE:
 In computing the length of the boom on Tower Cranes, they shall be measured from the base of the Tower to the point of the boom.

HAZMAT:
 Anyone working on HAZMAT jobs, working with supplied air shall receive \$1.00 an hour above classification.

 ENGI0612-012 06/01/2014

LEWIS, PIERCE, PACIFIC (portion lying north of a parallel line extending west from the northern boundary of Wahkaikum County to the sea) AND THURSTON COUNTIES

ON PROJECTS DESCRIBED IN FOOTNOTE A BELOW, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS. ON ALL OTHER WORK, THE FOLLOWING RATES APPLY.

Zone 1 (0-25 radius miles):

	Rates	Fringes
POWER EQUIPMENT OPERATOR		
GROUP 1A.....	\$ 38.39	17.40
GROUP 1AA.....	\$ 38.96	17.40
GROUP 1AAA.....	\$ 39.52	17.40
GROUP 1.....	\$ 37.84	17.40
GROUP 2.....	\$ 37.35	17.40
GROUP 3.....	\$ 36.93	17.40
GROUP 4.....	\$ 34.57	17.40

Zone Differential (Add to Zone 1 rates):
 Zone 2 (26-45 radius miles) = \$1.00
 Zone 3 (Over 45 radius miles) - \$1.30

BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1 AAA - Cranes-over 300 tons or 300 ft of boom (including jib with attachments)

GROUP 1AA - Cranes- 200 tonsto 300 tons, or 250 ft of boom (including jib with attachments; Tower crane over 175 ft in height, bas to boom

GROUP 1A - Cranes, 100 tons thru 199 tons, or 150 ft of boom (including jib with attachments); Crane-overhead, bridge type, 100 tons and over; Tower crane up to 175 ft in height base to boom; Loaders-overhead, 8 yards and over; Shovels, excavator, backhoes-6 yards and over with attachments

GROUP 1 - Cableway; Cranes 45 tons thru 99 tons under 150 ft of boom (including jib with attachments); Crane-overhead, bridge type, 45 tons thru 99 tons; Derricks on building work; Excavator, shovel, backhoes over 3 yards and under 6 yards; Hard tail end dump articulating off-road equipment 45 yards and over; Loader- overhead, 6 yards to, but not including, 8 yards; Mucking machine, mole, tunnel, drill and/or shield; Quad 9 HD 41, D-10; Remote control operator on rubber tired earth moving equipment; Rollagon; Scrapers-self-propelled 45 yards and over; Slipform pavers; Transporters, all track or truck type

GROUP 2 - Barrier machine (zipper); Batch Plant Operator-concrete; Bump Cutter; Cranes, 20 tons thru 44 tons with attachments; Crane-Overhead, bridge type, 20 tons through 44 tons; Chipper; Concrete pump-truck mount with boom attachment; Crusher; Deck engineer/deck winches (power); Drilling machine; Excavator, shovel, backhoe-3 yards and under; Finishing machine, Bidwell, Gamaco and similar equipment; Guardrail punch; Loaders, overhead under 6 yards; Loaders-plant feed; Locomotives-all; Mechanics- all; Mixers, asphalt plant; Motor patrol graders, finishing; Piledriver (other than crane mount); Roto-mill, roto-grinder; Screedman, spreader, topside operator-Blaw Knox, Cedar Rapids, Jaeger, Caterpillar, Barbar Green; Scraper-self-propelled, hard tail end dump, articulating off-road equipment- under 45 yards; Subgrader trimmer; Tractors, backhoe over 75 hp; Transfer material service machine-shuttle buggy, Blaw Knox- Roadtec; Truck Crane oiler/driver-100 tons and over; Truck Mount Portable Conveyor; Yo Yo pay

GROUP 3 - Conveyors; Cranes through 19 tons with attachments; Crane-A-frame over 10 tons; Drill oilers-auger type, truck or crane mount; Dozer-D-9 and under; Forklift-3000 lbs. and over with attachments; Horizontal/directional drill locator; Outside Hoists-(elevators and manlifts), air tuggers, strato tower bucket elevators; Hydralifts/boom trucks over 10 tons; Loaders-elevating type, belt; Motor patrol grader-nonfinishing; Plant oiler- asphalt, crusher; Pump-Concrete; Roller, plant mix or multi-lfit materials; Saws-concrete; Scrapers, concrete and carry all; Service engineers-equipment; Trenching machines; Truck crane oiler/driver under 100 tons; Tractors, backhoe under 75 hp

GROUP 4 - Assistant Engineer; Bobcat; Brooms; Compressor; Concrete Finish Machine-laser screed; Cranes A-frame 10 tons and under; Elevator and manlift (permanent and shaft type); Forklifts-under 3000 lbs. with attachments; Gradechecker, stakehop; Hydralifts/boom trucks, 10 tons and under; Oil distributors, blower distribution and mulch seeding operator; Pavement breaker; Posthole digger-mechanical; Power plant; Pumps-water; Rigger and Bellman; Roller-other than plant mix; Wheel Tractors, farmall type; Shotcrete/gunite equipment operator

- FOOTNOTE A- Reduced rates may be paid on the following:
1. Projects involving work on structures such as buildings and bridges whose total value is less than \$1.5 million excluding mechanical, electrical, and utility portions of the contract.
 2. Projects of less than \$1 million where no building is involved. Surfacing and paving included, but utilities excluded.
 3. Marine projects (docks, wharfs, etc.) less than \$150,000.

HANDLING OF HAZARDOUS WASTE MATERIALS: Personnel in all craft classifications subject to working inside a federally designated hazardous perimeter shall be eligible for compensation in accordance with the following group schedule relative to the level of hazardous waste as outlined in the specific hazardous waste project site safety plan.

H-1 Base wage rate when on a hazardous waste site when not outfitted with protective clothing, Class "D" Suit - Base wage rate plus \$.50 per hour.
 H-2 Class "C" Suit - Base wage rate plus \$1.00 per hour.
 H-3 Class "B" Suit - Base wage rate plus \$1.50 per hour.
 H-4 Class "A" Suit - Base wage rate plus \$2.00 per hour.

ENGI0701-002 01/01/2015

CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHIAKUM COUNTIES

POWER EQUIPMENT OPERATORS: ZONE 1

	Rates	Fringes
POWER EQUIPMENT OPERATOR		
GROUP 1.....	\$ 39.47	14.10
GROUP 1A.....	\$ 41.44	14.10
GROUP 1B.....	\$ 43.42	14.10
GROUP 2.....	\$ 37.58	14.10
GROUP 3.....	\$ 36.44	14.10
GROUP 4.....	\$ 35.36	14.10
GROUP 5.....	\$ 34.13	14.10
GROUP 6.....	\$ 30.94	14.10

Zone Differential (add to Zone 1 rates):
 Zone 2 - \$3.00
 Zone 3 - \$6.00

For the following metropolitan counties: MULTNOMAH;
CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA;
CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS
INDICATED:

All jobs or projects located in Multnomah, Clackamas and Marion Counties, West of the western boundary of Mt. Hood National Forest and West of Mile Post 30 on Interstate 84 and West of Mile Post 30 on State Highway 26 and West of Mile Post 30 on Highway 22 and all jobs or projects located in Yamhill County, Washington County and Columbia County and all jobs or projects located in Clark & Cowlitz County, Washington except that portion of Cowlitz County in the Mt. St. Helens "Blast Zone" shall receive Zone I pay for all classifications.

All jobs or projects located in the area outside the identified boundary above, but less than 50 miles from the Portland City Hall shall receive Zone II pay for all classifications.

All jobs or projects located more than 50 miles from the Portland City Hall, but outside the identified border above, shall receive Zone III pay for all classifications.

For the following cities: ALBANY; BEND; COOS BAY; EUGENE;
GRANTS PASS; KLAMATH FALLS; MEDFORD; ROSEBURG

All jobs or projects located within 30 miles of the respective city hall of the above mentioned cities shall receive Zone I pay for all classifications.

All jobs or projects located more than 30 miles and less than 50 miles from the respective city hall of the above mentioned cities shall receive Zone II pay for all classifications.

All jobs or projects located more than 50 miles from the respective city hall of the above mentioned cities shall receive Zone III pay for all classifications.

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

Group 1 Concrete Batch Plant and or Wet mix three (3) units or more;
Crane, Floating one hundred and fifty (150) ton but less than two hundred and fifty (250) ton; Crane, two hundred (200) ton through two hundred ninety nine (299) ton with two hundred foot (200') boom or less (including jib, inserts and/or attachments); Crane, ninety (90) ton through one hundred ninety nine (199) ton with over two hundred (200') boom Including jib, inserts and/or attachments); Crane, Tower Crane with one hundred seventy five foot (175') tower or less and with less than two hundred foot (200') jib; Crane, Whirley ninety (90) ton and over;
Helicopter when used in erecting work

Group 1A Crane, floating two hundred fifty (250) ton and over; Crane, two hundred (200) ton through two hundred ninety nine (299) ton, with over two hundred foot (200') boom (including jib, inserts and/or attachments); Crane, three hundred (300) ton through three hundred ninety nine (399) ton; Crane, Tower Crane with over one hundred seventy five foot (175') tower or over two hundred foot (200') jib;
Crane, tower Crane on rail system or 2nd tower or more in work radius

Group 1B Crane, three hundred (300) ton through three hundred ninety nine (399) ton, with over two hundred foot (200') boom (including jib, inserts and/or attachments); Floating crane, three hundred fifty (350) ton and over; Crane, four hundred (400) ton and over

Group 2 Asphalt Plant (any type); Asphalt Roto-Mill, pavement profiler eight foot (8') lateral cut and over; Auto Grader or "Trimmer"; Blade, Robotic; Bulldozer, Robotic Equipment (any type); Bulldozer, over one hundred twenty thousand (120,000) lbs. and above; Concrete Batch Plant and/or Wet Mix one (1) and two (2) drum; Concrete Diamond Head Profiler; Canal Trimmer; Concrete, Automatic Slip Form Paver (Assistant to the Operator required); Crane, Boom Truck fifty (50) ton and with over one hundred fifty foot (150') boom and over; Crane, Floating (derrick barge) thirty (30) ton but less than one hundred fifty (150) ton; Crane, Cableway twenty-five (25) ton and over; Crane, Floating Clamshell three (3) cu. Yds. And over; Crane, ninety (90) ton through one hundred ninety nine (199) ton up to and including two hundred foot (200') of boom (including jib inserts and/or attachments); Crane, fifty (50) ton through eighty nine (89) ton with over one hundred fifty foot (150') boom (including jib inserts and/or attachments); Crane, Whirley under ninety (90) ton; Crusher Plant; Excavator over one hundred thirty thousand (130,000) lbs.; Loader one hundred twenty thousand (120,000) lbs. and above; Remote Controlled Earth Moving Equipment; Shovel, Dragline, Clamshell, five (5) cu. Yds. And over; Underwater Equipment remote or otherwise, when used in construction work; Wheel Excavator any size

Group 3 Bulldozer, over seventy thousand (70,000) lbs. up to and including one hundred twenty thousand (120,000) lbs.; Crane, Boom Truck fifty (50) ton and over with less than one hundred fifty foot (150') boom; Crane, fifty (50) ton through eighty nine (89) ton with one hundred fifty foot (150') boom or less (including jib inserts and/or attachments); Crane, Shovel, Dragline or Clamshell three (3) cu. yds. but less than five (5) cu. Yds.; Excavator over eighty thousand (80,000) lbs. through one hundred thirty thousand (130,000) lbs.; Loader sixty thousand (60,000) lbs. and less than one hundred twenty thousand (120,000) lbs.

Group 4 Asphalt, Screed; Asphalt Paver; Asphalt Roto-Mill, pavement profiler, under eight foot (8') lateral cut; Asphalt, Material Transfer Vehicle Operator; Back Filling Machine; Backhoe, Robotic, track and wheel type up to and including twenty thousand (20,000) lbs. with any attachments; Blade (any type); Boatman; Boring Machine; Bulldozer over twenty thousand (20,000) lbs. and more than one hundred (100) horse up to seventy thousand (70,000) lbs.; Cable-Plow (any type); Cableway up to twenty five (25) ton; Cat Drill (John Henry); Chippers; Compactor, multi-engine; Compactor, Robotic; Compactor with blade self-propelled; Concrete, Breaker; Concrete, Grout Plant; Concrete, Mixer Mobile; Concrete, Paving Road Mixer; Concrete, Reinforced Tank Banding Machine; Crane, Boom Truck twenty (20) ton and under fifty (50) ton; Crane, Bridge Locomotive, Gantry and Overhead; Crane, Carry Deck; Crane, Chicago Boom and similar types; Crane, Derrick Operator, under one hundred (100) ton; Crane, Floating Clamshell, Dragline, etc. Operator, under three (3) cu. yds. Or less than thirty (30) ton; Crane, under fifty (50) ton; Crane, Quick Tower under one hundred foot (100') in height and less than one hundred fifty foot (150') jib (on rail included); Diesel-Electric Engineer (Plant or Floating); Directional Drill over twenty thousand (20,000) lbs. pullback; Drill Cat Operator; Drill Doctor and/or Bit Grinder; Driller, Percussion, Diamond, Core, Cable, Rotary and similar type; Excavator Operator over twenty thousand (20,000) lbs. through eighty thousand (80,000) lbs.; Generator Operator; Grade-all; Guardrail Machines, i.e. punch, auger, etc.; Hammer Operator (Piledriver); Hoist, stiff leg, guy derrick or similar type, fifty (50) ton and over; Hoist, two (2) drums or more; Hydro Axe (loader mounted or similar type); Jack Operator, Elevating Barges, Barge Operator, self-unloading; Loader Operator, front end and overhead, twenty five thousand (25,000) lbs. and less than sixty thousand (60,000) lbs.; Log Skidders; Piledriver Operator (not crane type); Pipe, Bending, Cleaning, Doping and Wrapping Machines; Rail, Ballast Tamper Multi-Purpose; Rubber-tired Dozers and Pushers; Scraper, all types; Side-Boom; Skip Loader, Drag Box; Strump Grinder (loader mounted or similar type); Surface Heater and Planer; Tractor, rubber-tired, over fifty (50) HP Flywheel; Trenching Machine three foot (3') depth and deeper; Tub Grinder (used for wood debris); Tunnel Boring Machine Mechanic; Tunnel, Mucking Machine;

Ultra High Pressure Water Jet Cutting Tool System Operator;
Vacuum Blasting Machine Operator; Water pulls, Water wagons

Group 5 Asphalt, Extrusion Machine; Asphalt, Roller (any asphalt mix); Asphalt, Roto-Mill pavement profiler ground man; Bulldozer, twenty thousand (20,000) lbs. or less, or one hundred (100) horse or less; Cement Pump; Chip Spreading Machine; Churn Drill and Earth Boring Machine; Compactor, self-propelled without blade; Compressor, (any power) one thousand two hundred fifty (1,250) cu. ft. and over, total capacity; Concrete, Batch Plant Quality control; Concrete, Combination Mixer and compressor operator, gunite work; Concrete, Curb Machine, Mechanical Berm, Curb and/or Curb and Gutter; Concrete, Finishing Machine; Concrete, Grouting Machine; Concrete, Internal Full Slab Vibrator Operator; Concrete, Joint Machine; Concrete, Mixer single drum, any capacity; Concrete, Paving Machine eight foot (8') or less; Concrete, Planer; Concrete, Pump; Concrete, Pump Truck; Concrete, Pumpcrete Operator (any type); Concrete, Slip Form Pumps, power driven hydraulic lifting device for concrete forms; Conveyored Material Hauler; Crane, Boom Truck under twenty (20) tons; Crane, Boom Type lifting device, five (5) ton capacity or less; Drill, Directional type less than twenty thousand (20,000) lbs. pullback; Fork Lift, over ten (10) ton or Robotic; Helicopter Hoist; Hoist Operator, single drum; Hydraulic Backhoe track type up to and including twenty thousand (20,000) lbs.; Hydraulic Backhoe wheel type (any make); Laser Screed; Loaders, rubber-tired type, less than twenty five thousand (25,000) lbs.; Pavement Grinder and/or Grooving Machine (riding type); Pipe, cast in place Pipe Laying Machine; Pulva-Mixer or similar types; Pump Operator, more than five (5) pumps (any size); Rail, Ballast Compactor, Regulator, or Tamper machines; Service Oiler (Greaser); Sweeper Self-Propelled; Tractor, Rubber-Tired, fifty (50) HP flywheel and under; Trenching Machine Operator, maximum digging capacity three foot (3') depth; Tunnel, Locomotive, Dinkey; Tunnel, Power Jumbo setting slip forms, etc.

Group 6 Asphalt, Pugmill (any type); Asphalt, Raker; Asphalt, Truck Mounted Asphalt Spreader, with Screed; Auger Oiler; Boatman; Bobcat, skid steed (less than one (1) yard); Broom, self-propelled; Compressor Operator (any power) under 1,250 cu. ft. total capacity; Concrete Curing Machine (riding type); Concrete Saw; Conveyor Operator or Assistant; Crane, Tugger; Crusher Feeder; Crusher Oiler; Deckhand; Drill, Directional Locator; Fork Lift; Grade Checker; Guardrail Punch Oiler; Hydrographic Seeder Machine, straw, pulp or seed; Hydrostatic Pump Operator; Mixer Box (CTB, dry batch, etc.); Oiler; Plant Oiler; Pump (any power); Rail, Brakeman, Switchman, Motorman; Rail, Tamping Machine, mechanical, self-propelled; Rigger; Roller grading (not asphalt); Truck, Crane Oiler-Driver

IRON0014-005 07/01/2015

ADAMS, ASOTIN, BENTON, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, LINCOLN, OKANOGAN, PEND ORIELLE, SPOKANE, STEVENS, WALLA WALLA AND WHITMAN COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 32.76	23.19

IRON0029-002 07/01/2015

CLARK, COWLITZ, KLINKITAT, PACIFIC, SKAMANIA, AND WAHKAIKUM COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 34.12	23.04

IRON0086-002 07/01/2015

YAKIMA, KITTITAS AND CHELAN COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 32.76	23.19

IRON0086-004 07/01/2015

CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PIERCE, SKAGIT, SNOHOMISH, THURSTON, AND WHATCOM COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 40.04	23.19

LABO0001-002 06/01/2014

ZONE 1:

	Rates	Fringes
Laborers:		
CALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (NORTH OF STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY WAHKAIAKUM COUNTY WEST TO THE PACIFIC OCEAN), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES		

GROUP 1.....	\$ 22.49	10.30
GROUP 2.....	\$ 25.79	10.30
GROUP 3.....	\$ 32.29	10.30
GROUP 4.....	\$ 33.08	10.30
GROUP 5.....	\$ 33.62	10.30

CHELAN, DOUGLAS (WEST OF THE 120TH MERIDIAN), KITTITAS AND YAKIMA COUNTIES

GROUP 1.....	\$ 18.95	10.30
GROUP 2.....	\$ 21.76	10.30
GROUP 3.....	\$ 23.85	10.30
GROUP 4.....	\$ 24.43	10.30
GROUP 5.....	\$ 24.85	10.30

BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON

ZONE 1 - Projects within 25 radius miles of the respective city hall
 ZONE 2 - More than 25 but less than 45 radius miles from the respective city hall
 ZONE 3 - More than 45 radius miles from the respective city hall

ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES):
 ZONE 2 - \$1.00
 ZONE 3 - \$1.30

BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA

ZONE 1 - Projects within 25 radius miles of the respective city hall
 ZONE 2 - More than 25 radius miles from the respective city hall

ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES):
 ZONE 2 - \$2.25

LABORERS CLASSIFICATIONS

GROUP 1: Landscaping and Planting; Watchman; Window Washer/Cleaner (detail clean-up, such as but not limited to cleaning floors, ceilings, walls, windows, etc., prior to final acceptance by the owner)

GROUP 2: Batch Weighman; Crusher Feeder; Fence Laborer; Flagman; Pilot Car

GROUP 3: General Laborer; Air, Gas, or Electric Vibrating Screed; Asbestos Abatement Laborer; Ballast Regulator Machine; Brush Cutter; Brush Hog Feeder; Burner; Carpenter Tender; Cement Finisher Tender; Change House or Dry Shack; Chipping Gun (under 30 lbs.); Choker Setter; Chuck Tender; Clean-up Laborer; Concrete Form Stripper; Curing Laborer; Demolition (wrecking and moving including charred material); Ditch Digger; Dump Person; Fine Graders; Firewatch; Form Setter; Gabian Basket Builders; Grout Machine Tender; Grinders; Guardrail Erector; Hazardous Waste Worker (Level C: uses a chemical "splash suit" and air purifying respirator); Maintenance Person; Material Yard Person; Pot Tender; Rip Rap Person; Riggers; Scale Person; Sloper Sprayer; Signal Person; Stock Piler; Stake Hopper; Toolroom Man (at job site); Topper-Tailer; Track Laborer; Truck Spotter; Vinyl Seamer

GROUP 4: Cement Dumper-Paving; Chipping Gun (over 30 lbs.); Clary Power Spreader; Concrete Dumper/Chute Operator; Concrete Saw Operator; Drill Operator (hydraulic, diamond, airtrac); Faller and Bucker Chain Saw; Grade Checker and Transit Person; Groutmen (pressure) including post tension beams; Hazardous Waste Worker (Level B: uses same respirator protection as Level A. A supplied air line is provided in conjunction with a chemical "splash suit"); High Scaler; Jackhammer; Laserbeam Operator; Manhole Builder-Mudman; Nozzleman (concrete pump, green cutter when using combination of high pressure air and water on concrete and rock, sandblast, gunite, shotcrete, water blaster, vacuum blaster); Pavement Breaker; Pipe Layer and Caulker; Pipe Pot Tender; Pipe Reliner (not insert type); Pipe Wrapper; Power Jacks; Railroad Spike Puller-Power; Raker-Asphalt; Rivet Buster; Rodder; Sloper (over 20 ft); Spreader (concrete); Tamper and Similar electric, air and gas operated tool; Timber Person-sewer (lagger shorer and cribber); Track Liner Power; Tugger Operator; Vibrator; Well Point Laborer

GROUP 5: Caisson Worker; Miner; Mortarman and Hodcarrier; Powderman; Re-Timberman; Hazardous Waste Worker (Level A: utilizes a fully encapsulated suit with a self-contained breathing apparatus or a supplied air line).

LABO0238-004 06/01/2014

PASCO AREA: ADAMS, BENTON, COLUMBIA, DOUGLAS (East of 120th Meridian), FERRY, FRANKLIN, GRANT, OKANOGAN, WALLA WALLA

SPOKANE AREA: ASOTIN, GARFIELD, LINCOLN, PEND OREILLE, SPOKANE, STEVENS & WHITMAN COUNTIES

	Rates	Fringes
LABORER (PASCO)		
GROUP 1.....	\$ 22.25	10.95
GROUP 2.....	\$ 24.35	10.95
GROUP 3.....	\$ 24.62	10.95
GROUP 4.....	\$ 24.89	10.95
GROUP 5.....	\$ 25.17	10.95
LABORER (SPOKANE)		
GROUP 1.....	\$ 21.95	10.95
GROUP 2.....	\$ 24.05	10.95
GROUP 3.....	\$ 24.32	10.95
GROUP 4.....	\$ 24.59	10.95
GROUP 5.....	\$ 24.87	10.95

Zone Differential (Add to Zone 1 rate): \$2.00

BASE POINTS: Spokane, Pasco, Lewiston

Zone 1: 0-45 radius miles from the main post office.
Zone 2: 45 radius miles and over from the main post office.

LABORERS CLASSIFICATIONS

GROUP 1: Flagman; Landscape Laborer; Scalemen; Traffic Control Maintenance Laborer (to include erection and maintenance of barricades, signs and relief of flagperson); Window Washer/Cleaner (detail cleanup, such as, but not limited to cleaning floors, ceilings, walls, windows, etc. prior to final acceptance by the owner)

GROUP 2: Asbestos Abatement Worker; Brush Hog Feeder; Carpenter Tender; Cement Handler; Clean-up Laborer; Concrete Crewman (to include stripping of forms, hand operating jacks on slip form construction, application of concrete curing compounds, pumpcrete machine, signaling, handling the nozzle of squeezecrete or similar machine, 6 inches and smaller); Confined Space Attendant; Concrete Signalman; Crusher Feeder; Demolition (to include clean-up, burning, loading, wrecking and salvage of all material); Dumpman; Fence Erector; Firewatch; Form Cleaning Machine Feeder, Stacker; General Laborer; Grout Machine Header Tender; Guard Rail (to include guard rails, guide and reference posts, sign posts, and right-of-way markers); Hazardous Waste Worker, Level D (no respirator is used and skin protection is minimal); Miner, Class "A" (to include all bull gang, concrete crewman, dumpman and pumpcrete crewman, including distributing pipe, assembly & dismantling, and nipper); Nipper; Riprap Man; Sandblast Tailhoseman; Scaffold Erector (wood or steel); Stake Jumper; Structural Mover (to include separating foundation, preparation, cribbing, shoring, jacking and unloading of structures); Tailhoseman (water nozzle); Timber Buckler and Faller (by hand); Track Laborer (RR); Truck Loader; Well-Point Man; All Other Work Classifications Not Specially Listed Shall Be Classified As General Laborer

GROUP 3: Asphalt Roller, walking; Cement Finisher Tender; Concrete Saw, walking; Demolition Torch; Dope Pot Firemen, non-mechanical; Driller Tender (when required to move and position machine); Form Setter, Paving; Grade Checker using level; Hazardous Waste Worker, Level C (uses a chemical "splash suit" and air purifying respirator); Jackhammer Operator; Miner, Class "B" (to include brakeman, finisher, vibrator, form setter); Nozzleman (to include squeeze and flo-crete nozzle); Nozzleman, water, air or steam; Pavement Breaker (under 90 lbs.); Pipelayer, corrugated metal culvert; Pipelayer, multi-plate; Pot Tender; Power Buggy Operator; Power Tool Operator, gas, electric, pneumatic; Railroad Equipment, power driven, except dual mobile power spiker or puller; Railroad Power Spiker or Puller, dual mobile; Rodder and Spreader; Tamper (to include operation of Barco, Essex and similar tampers); Trencher, Shawnee; Tugger Operator; Wagon Drills; Water Pipe Liner; Wheelbarrow (power driven)

GROUP 4: Air and Hydraulic Track Drill; Asphalt Raker; Brush Machine (to include horizontal construction joint cleanup brush machine, power propelled); Caisson Worker, free air; Chain Saw Operator and Faller; Concrete Stack (to include laborers when laborers working on free standing concrete stacks for smoke or fume control above 40 feet high); Gunite (to include operation of machine and nozzle); Hazardous Waste Worker, Level B (uses same respirator protection as Level A. A supplied air line is provided in conjunction with a chemical "splash suit"); High Scaler; Laser Beam Operator (to include grade checker and elevation control); Miner, Class C (to include miner, nozzleman for concrete, laser beam operator and rigger on tunnels); Monitor Operator (air track or similar mounting); Mortar Mixer; Nozzleman (to include jet blasting nozzleman, over 1,200 lbs., jet blast machine power propelled, sandblast nozzle); Pavement Breaker (90 lbs. and over); Pipelayer (to include working topman, caulker, collarman, jointer, mortarman, rigger, jacker, shorer, valve or meter installer); Pipewrapper; Plasterer Tender; Vibrators (all)

GROUP 5 - Drills with Dual Masts; Hazardous Waste Worker, Level A (utilizes a fully encapsulated suit with a self-contained breathing apparatus or a supplied air line); Miner Class "D", (to include raise and shaft miner, laser beam operator on riases and shafts)

LABO0238-006 06/01/2014

COUNTIES EAST OF THE 120TH MERIDIAN: ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, LINCOLN, OKANOGAN, PEND OREILLE, STEVENS, SPOKANE, WALLA WALLA, WHITMAN

	Rates	Fringes
Hod Carrier.....	\$ 24.32	10.95

LABO0335-001 06/01/2013

CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHAKIUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHAKIUM COUNTIES

	Rates	Fringes
Laborers:		
ZONE 1:		
GROUP 1.....	\$ 28.65	10.05
GROUP 2.....	\$ 29.25	10.05
GROUP 3.....	\$ 29.69	10.05
GROUP 4.....	\$ 30.07	10.05
GROUP 5.....	\$ 26.15	10.05
GROUP 6.....	\$ 23.73	10.05
GROUP 7.....	\$ 20.53	10.05

Zone Differential (Add to Zone 1 rates):

Zone 2 \$ 0.65
 Zone 3 - 1.15
 Zone 4 - 1.70
 Zone 5 - 2.75

BASE POINTS: GOLDENDALE, LONGVIEW, AND VANCOUVER

ZONE 1: Projects within 30 miles of the respective city all.
 ZONE 2: More than 30 miles but less than 40 miles from the respective city hall.
 ZONE 3: More than 40 miles but less than 50 miles from the respective city hall.
 ZONE 4: More than 50 miles but less than 80 miles from the respective city hall.
 ZONE 5: More than 80 miles from the respective city hall.

LABORERS CLASSIFICATIONS

GROUP 1: Asphalt Plant Laborers; Asphalt Spreaders; Batch Weighman; Broomers; Brush Burners and Cutters; Car and Truck Loaders; Carpenter Tender; Change-House Man or Dry Shack Man; Choker Setter; Clean-up Laborers; Curing, Concrete; Demolition, Wrecking and Moving Laborers; Dumpers, road oiling crew; Dumpmen (for grading crew); Elevator Feeders; Median Rail Reference Post, Guide Post, Right of Way Marker; Fine Graders; Fire Watch; Form Strippers (not swinging stages); General Laborers; Hazardous Waste Worker; Leverman or Aggregate Spreader (Flaherty and similar types); Loading Spotters; Material Yard Man (including electrical); Pittsburgh Chipper Operator or Similar Types; Railroad Track Laborers; Ribbon Setters (including steel forms); Rip Rap Man (hand placed); Road Pump Tender; Sewer Labor; Signalman; Skipman; Slopers; Spraymen; Stake Chaser; Stockpiler; Tie Back Shoring; Timber Faller and Bucker (hand labor); Toolroom Man (at job site); Tunnel Bullgang (above ground); Weight-Man- Crusher (aggregate when used)

GROUP 2: Applicator (including pot power tender for same), applying protective material by hand or nozzle on utility lines or storage tanks on project; Brush Cutters (power saw); Burners; Choker Splicer; Clary Power Spreader and similar types; Clean- up Nozzleman-Green Cutter (concrete, rock, etc.); Concrete Power Buggyman; Concrete Laborer; Crusher Feeder; Demolition and Wrecking Charred Materials; Gunite Nozzleman Tender; Gunite or Sand Blasting Pot Tender; Handlers or Mixers of all Materials of an irritating nature (including cement and lime); Tool Operators (includes but not limited to: Dry Pack Machine; Jackhammer; Chipping Guns; Paving Breakers); Pipe Doping and Wrapping; Post Hole Digger, air, gas or electric; Vibrating Screed; Tampers; Sand Blasting (Wet); Stake-Setter; Tunnel-Muckers, Brakemen, Concrete Crew, Bullgang (underground)

GROUP 3: Asbestos Removal; Bit Grinder; Drill Doctor; Drill Operators, air tracks, cat drills, wagon drills, rubber-mounted drills, and other similar types including at crusher plants; Gunite Nozzleman; High Scalars, Strippers and Drillers (covers work in swinging stages, chairs or belts, under extreme conditions unusual to normal drilling, blasting, barring-down, or sloping and stripping); Manhole Builder; Powdermen; Concrete Saw Operator; Pwdermen; Power Saw Operators (Bucking and Falling); Pumpcrete Nozzlemen; Sand Blasting (Dry); Sewer Timberman; Track Liners, Anchor Machines, Ballast Regulators, Multiple Tampers, Power Jacks, Tugger Operator; Tunnel-Chuck Tenders, Nippers and Timbermen; Vibrator; Water Blaster

GROUP 4: Asphalt Raker; Concrete Saw Operator (walls); Concrete Nozzelman; Grade Checker; Pipelayer; Laser Beam (pipelaying)-applicable when employee assigned to move, set up, align; Laser Beam; Tunnel Miners; Motorman-Dinky Locomotive-Tunnel; Powderman-Tunnel; Shield Operator-Tunnel

GROUP 5: Traffic Flaggers

GROUP 6: Fence Builders

GROUP 7: Landscaping or Planting Laborers

LABO0335-019 09/01/2013

	Rates	Fringes
Hod Carrier.....	\$ 30.47	10.05

* PAIN0005-002 07/01/2015

STATEWIDE EXCEPT CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES

	Rates	Fringes
Painters: STRIPERS.....	\$ 27.44	14.09

PAIN0005-004 03/01/2009

CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES

	Rates	Fringes
PAINTER.....	\$ 20.82	7.44

PAIN0005-006 07/01/2015

ADAMS, ASOTIN; BENTON AND FRANKLIN (EXCEPT HANFORD SITE);
CHELAN, COLUMBIA, DOUGLAS, FERRY, GARFIELD, GRANT, KITTITAS,
LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA,
WHITMAN AND YAKIMA COUNTIES

	Rates	Fringes
PAINTER		
Application of Cold Tar Products, Epoxies, Polyurethanes, Acids, Radiation Resistant Material, Water and Sandblasting.....	\$ 28.15	10.85
Over 30'/Swing Stage Work..	\$ 22.20	7.98
Brush, Roller, Striping, Steam-cleaning and Spray....	\$ 23.05	10.85
Lead Abatement, Asbestos Abatement.....	\$ 21.50	7.98

*\$.70 shall be paid over and above the basic wage rates listed for work on swing stages and high work of over 30 feet.

PAIN0055-003 07/01/2015

CLARK, COWLITZ, KLICKITAT, PACIFIC, SKAMANIA, AND WAHAKIYAKUM COUNTIES

	Rates	Fringes
PAINTER		
Brush & Roller.....	\$ 22.47	10.13
High work - All work 60 ft. or higher.....	\$ 23.22	10.13
Spray and Sandblasting.....	\$ 23.07	10.13

PAIN0055-006 11/01/2014

CLARK, COWLITZ, KLICKITAT, SKAMANIA and WAHAKIYAKUM COUNTIES

	Rates	Fringes
Painters:		
HIGHWAY & PARKING LOT STRIPER.....	\$ 33.43	11.08

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

* PLAS0072-004 06/01/2015

ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
ZONE 1.....	\$ 27.01	12.59

Zone Differential (Add to Zone 1 rate): Zone 2 - \$2.00

BASE POINTS: Spokane, Pasco, Lewiston; Wenatchee
Zone 1: 0 - 45 radius miles from the main post office
Zone 2: Over 45 radius miles from the main post office

PLAS0528-001 06/01/2015

CLALLAM, COWLITZ, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON, WAHAKIYAKUM AND WHATCOM COUNTIES

	Rates	Fringes
CEMENT MASON		
CEMENT MASON.....	\$ 38.52	15.43
COMPOSITION, TROWEL MACHINE, GRINDER, POWER TOOLS, GUNNITE NOZZLE.....	\$ 39.02	15.43
TROWLING MACHINE OPERATOR ON COMPOSITION.....	\$ 39.02	15.43

PLAS0555-002 06/01/2015

CLARK, KLICKITAT AND SKAMANIA COUNTIES

ZONE 1:

	Rates	Fringes
CEMENT MASON		
CEMENT MASONS DOING BOTH COMPOSITION/POWER MACHINERY AND SUSPENDED/HANGING SCAFFOLD..	\$ 30.58	18.18
CEMENT MASONS ON SUSPENDED, SWINGING AND/OR HANGING SCAFFOLD.....	\$ 30.58	18.18
CEMENT MASONS.....	\$ 29.98	18.18
COMPOSITION WORKERS AND POWER MACHINERY OPERATORS...	\$ 31.18	18.18

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

Zone Differential (Add To Zone 1 Rates):

Zone 2 - \$0.65
 Zone 3 - 1.15
 Zone 4 - 1.70
 Zone 5 - 3.00

BASE POINTS: BEND, CORVALLIS, EUGENE, MEDFORD, PORTLAND,
 SALEM, THE DALLES, VANCOUVER

ZONE 1: Projects within 30 miles of the respective city hall
 ZONE 2: More than 30 miles but less than 40 miles from the
 respective city hall.
 ZONE 3: More than 40 miles but less than 50 miles from the
 respective city hall.
 ZONE 4: More than 50 miles but less than 80 miles from the
 respective city hall.
 ZONE 5: More than 80 miles from the respective city hall

 TEAM0037-002 06/01/2014

CLARK, COWLITZ, KLICKITAT, PACIFIC (South of a straight line
 made by extending the north boundary line of Wahkiakum County
 west to the Pacific Ocean), SKAMANIA, AND WAHAKIYAKUM COUNTIES

Rates Fringes

Truck drivers:

	Rates	Fringes
ZONE 1		
GROUP 1.....	\$ 26.90	14.37
GROUP 2.....	\$ 27.02	14.37
GROUP 3.....	\$ 27.15	14.37
GROUP 4.....	\$ 27.41	14.37
GROUP 5.....	\$ 27.63	14.37
GROUP 6.....	\$ 27.79	14.37
GROUP 7.....	\$ 27.99	14.37

Zone Differential (Add to Zone 1 Rates):

Zone 2 - \$0.65
 Zone 3 - 1.15
 Zone 4 - 1.70
 Zone 5 - 2.75

BASE POINTS: ASTORIA, THE DALLES, LONGVIEW AND VANCOUVER

ZONE 1: Projects within 30 miles of the respective city
 hall.
 ZONE 2: More than 30 miles but less than 40 miles from the
 respective city hall.
 ZONE 3: More than 40 miles but less than 50 miles from the
 respective city hall.
 ZONE 4: More than 50 miles but less than 80 miles from the
 respective city hall.
 ZONE 5: More than 80 miles from the respective city hall.

TRUCK DRIVERS CLASSIFICATIONS

GROUP 1: A Frame or Hydra lift truck w/load bearing
 surface; Articulated Dump Truck; Battery Rebuilders; Bus or
 Manhaul Driver; Concrete Buggies (power operated); Concrete
 Pump Truck; Dump Trucks, side, end and bottom dumps,
 including Semi Trucks and Trains or combinations there of:
 up to and including 10 cu. yds.; Lift Jitneys, Fork Lifts
 (all sizes in loading, unloading and transporting material
 on job site); Loader and/or Leverman on Concrete Dry Batch
 Plant (manually operated); Pilot Car; Pickup Truck; Solo
 Flat Bed and misc. Body Trucks, 0-10 tons; Truck Tender;
 Truck Mechanic Tender; Water Wagons (rated capacity) up to
 3,000 gallons; Transit Mix and Wet or Dry Mix - 5 cu. yds.
 and under; Lubrication Man, Fuel Truck Driver, Tireman,
 Wash Rack, Steam Cleaner or combinations; Team Driver;
 Slurry Truck Driver or Leverman; Tireman

GROUP 2: Boom Truck/Hydra-lift or Retracting Crane;
 Challenger; Dumpsters or similar equipment all sizes; Dump
 Trucks/Articulated Dumps 6 cu to 10 cu.; Flaherty Spreader
 Driver or Leverman; Lowbed Equipment, Flat Bed Semi-trailer
 or doubles transporting equipment or wet or dry materials;
 Lumber Carrier, Driver-Straddle Carrier (used in loading,
 unloading and transporting of materials on job site); Oil
 Distributor Driver or Leverman; Transit mix and wet or dry
 mix trucks: over 5 cu. yds. and including 7 cu. yds.;
 Vacuum Trucks; Water truck/Wagons (rated capacity) over
 3,000 to 5,000 gallons

GROUP 3: Ammonia Nitrate Distributor Driver; Dump trucks,
 side, end and bottom dumps, including Semi Trucks and
 Trains or combinations thereof: over 10 cu. yds. and
 including 30 cu. yds. includes Articulated Dump Trucks;
 Self-Propelled Street Sweeper; Transit mix and wet or dry
 mix truck: over 7 cu yds. and including 11 cu yds.; Truck
 Mechanic-Welder-Body Repairman; Utility and Clean-up Truck;
 Water Wagons (rated capacity) over 5,000 to 10,000 gallons

GROUP 4: Asphalt Burner; Dump Trucks, side, end and bottom
 cumps, including Semi-Trucks and Trains or combinations
 thereof: over 30 cu. yds. and including 50 cu. yds.
 includes Articulated Dump Trucks; Fire Guard; Transit Mix
 and Wet or Dry Mix Trucks, over 11 cu. yds. and including
 15 cu. yds.; Water Wagon (rated capacity) over 10,000
 gallons to 15,000 gallons

GROUP 5: Composite Crewman; Dump Trucks, side, end and
 bottom dumps, including Semi Trucks and Trains or
 combinations thereof: over 50 cu. yds. and including 60 cu.
 yds. includes Articulated Dump Trucks

GROUP 6: Bulk Cement Spreader w/o Auger; Dry Pre-Batch
 concrete Mix Trucks; Dump trucks, side, end and bottom
 dumps, including Semi Trucks and Trains of combinations
 thereof: over 60 cu. yds. and including 80 cu. yds., and
 includes Articulated Dump Trucks; Skid Truck

GROUP 7: Dump Trucks, side, end and bottom dumps, including Semi Trucks and Trains or combinations thereof: over 80 cu. yds. and including 100 cu. yds., includes Articulated Dump Trucks; Industrial Lift Truck (mechanical tailgate)

TEAM0174-001 01/01/2014

CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (North of a straight line made by extending the north boundary line of Wahkiakum County west to the Pacific Ocean), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES

Rates Fringes

Truck drivers:

ZONE A:

GROUP 1:.....	\$ 32.18	16.69
GROUP 2:.....	\$ 31.34	16.69
GROUP 3:.....	\$ 28.53	16.69
GROUP 4:.....	\$ 23.56	16.69
GROUP 5:.....	\$ 31.73	16.69

ZONE B (25-45 miles from center of listed cities*): Add \$.70 per hour to Zone A rates.

ZONE C (over 45 miles from centr of listed cities*): Add \$1.00 per hour to Zone A rates.

*Zone pay will be calculated from the city center of the following listed cities:

BELLINGHAM	CENTRALIA	RAYMOND	OLYMPIA
EVERETT	SHELTON	ANACORTES	BELLEVIEWE
SEATTLE	PORT ANGELES	MT. VERNON	KENT
TACOMA	PORT TOWNSEND	ABERDEEN	BREMERTON

TRUCK DRIVERS CLASSIFICATIONS

GROUP 1 - "A-frame or Hydralift" trucks and Boom trucks or similar equipment when "A" frame or "Hydralift" and Boom truck or similar equipment is used; Buggymobile; Bulk Cement Tanker; Dumpsters and similar equipment, Tournorockers, Tournowagon, Tournotrailer, Cat DW series, Terra Cobra, Le Tourneau, Westinghouse, Athye Wagon, Euclid Two and Four-Wheeled power tractor with trailer and similar top-loaded equipment transporting material: Dump Trucks, side, end and bottom dump, including semi-trucks and trains or combinations thereof with 16 yards to 30 yards capacity: Over 30 yards \$.15 per hour additional for each 10 yard increment; Explosive Truck (field mix) and similar equipment; Hyster Operators (handling bulk loose aggregates); Lowbed and Heavy Duty Trailer; Road Oil Distributor Driver; Spreader, Flaherty Transit mix used exclusively in heavy construction; Water Wagon and Tank Truck-3,000 gallons and over capacity

GROUP 2 - Bulllifts, or similar equipment used in loading or unloading trucks, transporting materials on job site; Dumpsters, and similar equipment, Tournorockers, Tournowagon, Turnotrailer, Cat. D.W. Series, Terra Cobra, Le Tourneau, Westinghouse, Athye wagon, Euclid two and four-wheeled power tractor with trailer and similar top-loaded equipment transporting material: Dump trucks, side, end and bottom dump, including semi-trucks and trains or combinations thereof with less than 16 yards capacity; Flatbed (Dual Rear Axle); Grease Truck, Fuel Truck, Greaser, Battery Service Man and/or Tire Service Man; Leverman and loader at bunkers and batch plants; Oil tank transport; Scissor truck; Slurry Truck; Sno-Go and similar equipment; Swampers; Straddler Carrier (Ross, Hyster) and similar equipment; Team Driver; Tractor (small, rubber-tired)(when used within Teamster jurisdiction); Vacuum truck; Water Wagon and Tank trucks-less than 3,000 gallons capacity; Winch Truck; Wrecker, Tow truck and similar equipment

GROUP 3 - Flatbed (single rear axle); Pickup Sweeper; Pickup Truck. (Adjust Group 3 upward by \$2.00 per hour for onsite work only)

GROUP 4 - Escort or Pilot Car

GROUP 5 - Mechanic

HAZMAT PROJECTS

Anyone working on a HAZMAT job, where HAZMAT certification is required, shall be compensated as a premium, in addition to the classification working in as follows:
LEVEL C: +\$.25 per hour - This level uses an air purifying respirator or additional protective clothing.
LEVEL B: +\$.50 per hour - Uses same respirator protection as Level A. Supplied air line is provided in conjunction with a chemical "splash suit."
LEVEL A: +\$.75 per hour - This level utilizes a fully-encapsulated suit with a self-contained breathing apparatus or a supplied air line.

TEAM0690-004 01/01/2014

ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES

Rates Fringes

Truck drivers: (AREA 1: SPOKANE ZONE CENTER: Adams, Chelan, Douglas, Ferry, Grant, Kittitas, Lincoln, Okanogan, Pen Oreille, Spokane, Stevens, and Whitman Counties

AREA 1: LEWISTON ZONE CENTER: Asotin, Columbia, and Garfield Counties

AREA 2: PASCO ZONE CENTER: Benton, Franklin, Walla Walla and Yakima Counties)

GROUP	Rates	Fringes
AREA 1:		
GROUP 1	\$ 20.17	15.19
GROUP 2	\$ 22.44	15.19
GROUP 3	\$ 22.94	15.19
GROUP 4	\$ 23.27	15.19
GROUP 5	\$ 23.38	15.19
GROUP 6	\$ 23.55	15.19
GROUP 7	\$ 24.08	15.19
GROUP 8	\$ 24.44	15.19
AREA 2		
GROUP 1	\$ 21.77	15.19
GROUP 2	\$ 24.31	15.19
GROUP 3	\$ 24.42	15.19
GROUP 4	\$ 24.75	15.19
GROUP 5	\$ 24.86	15.19
GROUP 6	\$ 25.02	15.19
GROUP 7	\$ 25.56	15.19
GROUP 8	\$ 25.88	15.19

Zone Differential (Add to Zone 1 rate: Zone 1 + \$2.00)

BASE POINTS: Spokane, Pasco, Lewiston
Zone 1: 0-45 radius miles from the main post office.
Zone 2: Outside 45 radius miles from the main post office

TRUCK DRIVERS CLASSIFICATIONS

GROUP 1: Escort Driver or Pilot Car; Employee Haul; Power Boat Hauling Employees or Material

GROUP 2: Fish Truck; Flat Bed Truck; Fork Lift (3000 lbs. and under); Leverperson (loading trucks at bunkers); Tractor Mounted Hydro Seeder and Mulcher; Seeder & Mulcher; Stationary Fuel Operator; Tractor (small, rubber-tired, pulling trailer or similar equipment)

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

GROUP 3: Auto Crane (2000 lbs. capacity); Buggy Mobile & Similar; Bulk Cement Tanks & Spreader; Dumptor (6 yds. & under); Flat Bed Truck with Hydraulic System; Fork Lift (3001-16,000 lbs.); Fuel Truck Driver, Steamcleaner & Washer; Power Operated Sweeper; Rubber-tired Tunnel Jumbo; Scissors Truck; Slurry Truck Driver; Straddle Carrier (Ross, Hyster, & similar); Tireperson; Transit Mixers & Truck Hauling Concrete (3 yd. to & including 6 yds.); Trucks, side, end, bottom & articulated end dump (3 yards to and including 6 yds.); Warehouseperson (to include shipping & receiving); Wrecker & Tow Truck

GROUP 4: A-Frame; Burner, Cutter, & Welder; Service Greaser; Trucks, side, end, bottom & articulated end dump (over 6 yards to and including 12 yds.); Truck Mounted Hydro Seeder; Warehouseperson; Water Tank truck (0-8,000 gallons)

GROUP 5: Dumptor (over 6 yds.); Lowboy (50 tons & under); Self-loading Roll Off; Semi-Truck & Trailer; Tractor with Steer Trailer; Transit Mixers and Trucks Hauling Concrete (over 6 yds. to and including 10 yds.); Trucks, side, end, bottom and end dump (over 12 yds. to & including 20 yds.); Truck-Mounted Crane (with load bearing surface either mounted or pulled, up to 14 ton); Vacuum Truck (super sucker, guzzler, etc.)

GROUP 6: Flaherty Spreader Box Driver; Flowboys; Fork Lift (over 16,000 lbs.); Dumps (Semi-end); Mechanic (Field); Semi-end Dumps; Transfer Truck & Trailer; Transit Mixers & Trucks Hauling Concrete (over 10 yds. to & including 20 yds.); Trucks, side, end, bottom and articulated end dump (over 20 yds. to & including 40 yds.); Truck and Pup; Tournarocker, DWs & similar with 2 or more 4 wheel-power tractor with trailer, gallonage or yardage scale, whichever is greater Water Tank Truck (8,001- 14,000 gallons); Lowboy(over 50 tons)

GROUP 7: Oil Distributor Driver; Stringer Truck (cable operated trailer); Transit Mixers & Trucks Hauling Concrete (over 20 yds.); Truck, side, end, bottom end dump (over 40 yds. to & including 100 yds.); Truck Mounted Crane (with load bearing surface either mounted or pulled (16 through 25 tons);

GROUP 8: Prime Movers and Stinger Truck; Trucks, side, end, bottom and articulated end dump (over 100 yds.); Helicopter Pilot Hauling Employees or Materials

Footnote A - Anyone working on a HAZMAT job, where HAZMAT certification is required, shall be compensated as a premium, in addition to the classification working in as follows:

LEVEL C-D: - \$.50 PER HOUR (This is the lowest level of protection. This level may use an air purifying respirator or additional protective clothing.

WA150001 Modification 13
Federal Wage Determinations for Highway Construction

LEVEL A-B: - \$1.00 PER HOUR (Uses supplied air in conjunction with a chemical splash suit or fully encapsulated suit with a self-contained breathing apparatus.

Employees shall be paid Hazmat pay in increments of four(4) and eight(8) hours.

NOTE:

Trucks Pulling Equipment Trailers: shall receive \$.15/hour over applicable truck rate

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
 Wage and Hour Division
 U.S. Department of Labor
 200 Constitution Avenue, N.W.
 Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
 U.S. Department of Labor
 200 Constitution Avenue, N.W.
 Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
 U.S. Department of Labor
 200 Constitution Avenue, N.W.
 Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION

Bidder

To: Board of County Commissioners, Whitman County Courthouse, Colfax, WA
99111

Commissioners:

The undersigned hereby certify that they have examined the locations of the COUNTYWIDE OVERLAYS 3: C.R.P. No. 0017-2 located in Section 11, Township 20 North, Range 43 East, W.M., C.R.P. No. 0025-3 located in Sections 10, 11, 15, 22, 23 and 26, Township 20 North, Range 43 East, W.M., and C.R.P. No. 2500-8 located in Sections 3, 4, 9, 16, 17, 18 and 19, Township 17 North, Range 44 East, W.M., Sections 25, 26, 34 and 35, Township 18 North, Range 44 East, W.M., and Sections 19, 20, 29 and 30, Township 18 North, Range 45 East, W.M. and have read and thoroughly understand the plans, specifications and special provisions concerning the work described in this project.

The undersigned further understand the method by which payment will be made for said work, and hereby propose to undertake and complete the work described in this project, or as much thereof as can be completed with the monies available, in accordance with the said plans, specifications and special provisions and the following schedule of rates and prices:

SCHEDULE OF ITEMS

NOTE: Unit prices for all items (unless filled in by Contracting Agency), all extensions, and total amount of bid shall be shown. All entries must be in legible figures (not words) and typed or entered in ink.

ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT	PRICE PER UNIT	TOTAL PRICE
1.	MOBILIZATION	1	L.S.	LUMP SUM	
2.	REMOVING TEMPORARY PAVEMENT MARKING	18,691	L.F.		
3.	CRUSHED SURFACING TOP COURSE	2,310	TON		
4.	ASPHALT EMULSION CRS-2P	352	TON		
5.	ASPHALT FOR FOG SEAL	87	TON		
6.	FURNISHING AND PLACING CRUSHED 3/8" CHIPS	2,420	TON		
7.	HMA FOR PRELEVELING CL. 1/2 IN. PG 64-28	2,410	TON		
8.	HMA CL. 1/2 IN. PG 64-28	4,450	TON		
9.	JOB MIX COMPLIANCE PRICE ADJUSTMENT	1	CALC	(\$1.00)	(\$1.00)
10.	COMPACTION PRICE ADJUSTMENT	1	CALC	(\$1.00)	(\$1.00)
11.	PAVEMENT REINFORCEMENT GRID	19,000	S.Y.		
12.	PAINT LINE	196,954	L.F.		
13.	PAINTED STOP LINE	90	L.F.		
14.	PAINTED RAILROAD CROSSING SYMBOL	2	EACH		
15.	TEMPORARY PAVEMENT MARKING – SHORT DURATION	139,804	L.F.		
16.	PROJECT TEMPORARY TRAFFIC CONTROL	1	L.S.	LUMP SUM	
17.	CONSTRUCTION SIGNS CLASS A	1,498	S.F.		
18.	TRIMMING AND CLEANUP	1	L.S.	LUMP SUM	
19.	SPCC PLAN	1	L.S.	LUMP SUM	
BASIS OF AWARD: TOTAL BID ITEMS 1-19					

Failure to return this Declaration as part of the bid proposal package will make the bid nonresponsive and ineligible for award.

NON-COLLUSION DECLARATION

I, by signing the proposal, hereby declare, under penalty of perjury under the laws of the United States that the following statements are true and correct:

1. That the undersigned person(s), firm, association or corporation has (have) not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the project for which this proposal is submitted.
2. **That by signing the signature page of this proposal, I am deemed to have signed and to have agreed to the provisions of this declaration.**

NOTICE TO ALL BIDDERS

To report rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (USDOT) operates the above toll-free “hotline” Monday through Friday, 8:00 a.m. to 5:00 p.m., eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the “hotline” to report such activities.

The “hotline” is part of USDOT’s continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the USDOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Local Agency Certification for Federal-Aid Contracts

The prospective participant certifies by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

(1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan or cooperative agreement.

(2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

This certification is material representation of the fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, Title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each failure.

The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such subrecipients shall certify and disclose accordingly.

Bidder,

The Washington State Department of Transportation has made significant changes to the process for submitting Disadvantaged Business Enterprise (DBE) Condition of Award (COA) Goal documentation. Review the (DBE) specifications in the contract you are bidding for changes in the requirements. A partial list of changes is included in this letter. Failure to submit DBE documentation as required by the specifications will result in your bid being considered nonresponsive and will be rejected.

YOU MUST INCLUDE IN YOUR BID:

1. A Disadvantaged Business Enterprise Utilization Certification (WSDOT Form #272-056A EF Revised 07/2011) which demonstrates how you will meet the DBE COA Goal. Be sure to review the instructions for filling out the form. To assist you in selecting DBE firms, WSDOT and OMWBE have created a Directory of Certified DBE Firms, available at: <http://www.omwbe.wa.gov/certification/index.shtml>. This directory provides a "WSDOT COA Work Description" for each DBE firm for purposes of filling out the form. The "Description of Work" on the Disadvantaged Business Enterprise Utilization Certification must be consistent with the "WSDOT COA Work Description" in the Directory of Certified DBE Firms or your bid will be rejected, however do not copy the work description verbatim if it includes items of work in its title that are not work items of the contract. Only list those items of work in the Description of Work descriptor that the DBE Subcontractor is going to perform on the Contract. For example, if the Contract has work in installation and removal of pavement markings along with striping and you found a certified DBE Subcontractor that has a "WSDOT COA Work Description" of a descriptor such as, PAVEMENT MARKINGS INSTALLATION AND REMOVAL; INCLUDING STRIPING, GUIDEPOSTS, GLARE SHIELDS, BOLLARDS, RUMBLE STRIPS. If the Contract does not have work items for guideposts, glare shields, bollards and rumble strips then shorten the descriptor to only those work items in the descriptor that the DBE Subcontractor will be doing such as, PAVEMENT MARKINGS INSTALLATION AND REMOVAL; INCLUDING STRIPING.

2. You must submit a Disadvantaged Business Enterprise (DBE) Written Confirmation Document (dated 07/2011) for each DBE listed on your Disadvantaged Business Enterprise Utilization Certification. WSDOT has created Form # 422-031A EF for this purpose. Keep in mind that bidders and DBEs may have a supply of the old forms. Do not use them. Required information has been added to this form therefore use of an earlier version of the form may result in bid rejection. The "Description of Work" and "Amount to be Applied Towards Goal" listed the Disadvantaged Business Enterprise (DBE) Written Confirmation Document must match the "Description of Work" and "Amount to be Applied Towards Goal" listed on your Disadvantaged Business Enterprise Utilization Certification or your bid will be rejected. See Special Provision **Delivery Of Proposal** when this document needs to be submitted.

3. You must submit Good Faith Effort (GFE) Documentation in addition to the Disadvantaged Business Enterprise Utilization Certification ONLY IN THE EVENT your efforts to solicit sufficient DBE participation have been unsuccessful and you are relying upon your Good Faith Effort Documentation in whole or part to meet the goal. See Special Provision **Delivery of Proposal** when this document needs to be submitted.

WSDOT has posted a copy of our training materials on our website which is available at: <http://www.wsdot.wa.gov/biz/construction/> see "Construction News."

The Directory of Certified DBE Firms is available at: <http://www.omwbe.wa.gov/certification/index.shtml>

WSDOT Forms are available at: <http://www.wsdot.wa.gov/forms/>
Note the form # to easily locate the form.

Office of Equal Opportunity:
<http://www.wsdot.wa.gov/equalopportunity>

Contract Ad & Award:
<http://www.wsdot.wa.gov/biz/contaa/>

Local Agency Disadvantaged Business Enterprise Utilization Certification

To be eligible for award of this contract the bidder must fill out and submit, as part of its bid proposal, the following Disadvantaged Business Enterprise Utilization Certification relating to Disadvantaged Business Enterprise (DBE) requirements. The Contracting Agency shall consider as non-responsive and shall reject any bid proposal that does not contain a DBE Certification which properly demonstrates that the bidder will meet the DBE participation requirements in one of the manners provided for in the proposed contract. The Bidder must submit good faith effort documentation ***only in the event*** the bidder's efforts to solicit sufficient DBE participation has been unsuccessful. The successful bidder's Disadvantage Business Enterprise Utilization Certification shall be deemed a part of the resulting contract. Information on certified firms is available from OMWBE online at: <http://omwbe.wa.gov/directory-of-certified-firms/>

_____ certifies that the Disadvantaged Business Enterprise (DBE)
(Box 1) Name of Bidder

Firms listed below have been contacted regarding participation on this project. If this bidder is successful on this project and is awarded the contract, it shall assure that subcontracts or supply agreements are executed with those firms where an "Amount to be Applied Towards Goal" is listed. (If necessary, use additional sheet.)

Column 1 Name of DBE Certificate Number	Column 2 * Project Role (Prime, Joint Venture, Subcontractor, Manufacturer, Regular Dealer)	Column 3 Description of Work	Column 4 ** Amount to be Applied Towards Goal
1.			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			

Disadvantaged Business Enterprise Subcontracting Goal: _____ DBE Total \$ _____
Box 2 Box 3

* Regular Dealer status must be approved prior to bid submittal by the Office of Equal Opportunity, Wash. State Dept. of Transportation, on each contract.

** See the section "Crediting DBE Participation Toward Meeting the Goal" in the Contract Document.

*** The Contracting Agency will utilize this amount to determine whether or not the bidder has met the goal. In the event of an arithmetic difference between this total and the sum of the individual amounts listed above, then the sum of the amounts listed shall prevail and the total will be revised accordingly. Participation in excess of the goal amount will be considered voluntary or race-neutral participation.

Local Agency Disadvantaged Business Enterprise (DBE) Written Confirmation Document

As an authorized representative of the Disadvantaged Business Enterprise (DBE), I confirm that we have been contacted by the referenced bidder with regard to the referenced project and if the bidder is awarded the contract we will enter into an agreement with the bidder to participate in the project consistent with the information provided in the bidder's Disadvantaged Business Enterprise Utilization Certification.

Contract Title: _____

Bidder's Business Name: _____

DBE's Business Name: _____

DBE Signature: _____

DBE's Title: _____

Date: _____

The entries must be consistent with what is shown on the bidder's Disadvantaged Business Enterprise Utilization Certification. Failure to do so will result in bid rejection. See contract provision; *Disadvantaged Business Enterprise Condition of Award Participation*.

Description of Work: _____

Amount to be Applied Towards Goal: _____

Local Agency Name Whitman County
Local Agency Address

Local Agency Subcontractor List

Prepared in compliance with RCW 39.30.060 as amended

To Be Submitted with the Bid Proposal

Project Name _____

Failure to list subcontractors with whom the bidder, if awarded the contract, will directly subcontract for performance of the work of heating, ventilation and air conditioning, plumbing, as described in Chapter 18.106 RCW, and electrical, as described in Chapter 19.28 RCW or naming more than one subcontractor to perform the same work will result in your bid being non-responsive and therefore void.

Subcontractor(s) with whom the bidder will directly subcontract that are proposed to perform the work of heating, ventilation and air conditioning, plumbing, as described in Chapter 18.106 RCW, and electrical as described in Chapter 19.28 RCW **must** be listed below. The work to be performed is to be listed below the subcontractor(s) name.

To the extent the Project includes one or more categories of work referenced in RCW 39.30.060, and no subcontractor is listed below to perform such work, the bidder certifies that the work will either (i) be performed by the bidder itself, or (ii) be performed by a lower tier subcontractor who will not contract directly with the bidder.

Subcontractor Name _____
 Work to be Performed _____

Subcontractor Name _____
 Work to be Performed _____

Subcontractor Name _____
 Work to be Performed _____

Subcontractor Name _____
 Work to be Performed _____

Subcontractor Name _____
 Work to be Performed _____

* Bidder's are notified that is the opinion of the enforcement agency that PVC or metal conduit, junction boxes, etc, are considered electrical equipment and therefore considered part of electrical work, even if the installation is for future use and no wiring or electrical current is connected during the project.

Local Agency Proposal - Signature Page

The bidder is hereby advised that by signature of this proposal he/she is deemed to have acknowledged all requirements and signed all certificates contained herein.

A proposal guaranty in an amount of five percent (5%) of the total bid, based upon the approximate estimate of quantities at the above prices and in the form as indicated below is attached hereto:

- Cash In the Amount of _____
- Cashier's Check _____ Dollars
- Certified Check (\$ _____) Payable to the Agency
- Proposal Bond In the Amount of 5% of the Bid

Receipt is hereby acknowledged of addendum(s) No.(s) _____ , _____ & _____

Signature of Authorized Official(s)

Proposal Must be Signed 

Firm Name

Address

State of Washington Contractor's License No. _____

Federal ID No. _____

Note:

- (1) This proposal form is not transferable and any alteration of the firm's name entered hereon without prior permission from the Whitman County will be cause for considering the proposal irregular and subsequent rejection of the bid.
- (2) Please refer to section 1-02.6 of the standard specifications, re: "Preparation of Proposal," or "Article 4" of the Instruction to Bidders for building construction jobs.

**SUBMIT THE
ENCLOSED PROPOSAL
BOND FORM WITH
YOUR PROPOSAL.**

**USE OF OTHER FORMS
MAY SUBJECT YOUR
BID TO REJECTION.**

**NOTE: Use of other forms may limit
the bond below an amount equal
to five percent of the bid total.**

Local Agency Proposal Bond

KNOW ALL MEN BY THESE PRESENTS, That we,

of _____ as principal, and the

a corporation duly organized under the laws of the state of _____, and

authorized to do business in the State of Washington, as surety, are held and firmly bound unto the State of Washington in the full and penal sum of five (5) percent of the total amount of the bid proposal of said principal for the work hereinafter described, for the payment of which, well and truly to be made, we bind our heirs, executors, administrators and assigns, and successors and assigns, firmly by these presents.

The condition of this bond is such, that whereas the principal herein is herewith submitting his or its sealed proposal for the following highway construction, to wit:

said bid and proposal, by reference thereto, being made a part hereof.

NOW, THEREFORE, If the said proposal bid by said principal be accepted, and the contract be awarded to said principal, and if said principal shall duly make and enter into and execute said contract and shall furnish bond as required by the Whitman County within a period of twenty (20) days from and after said award, exclusive of the day of such award, then this obligation shall be null and void, otherwise it shall remain and be in full force and effect.

IN TESTIMONY WHEREOF, The principal and surety have caused these presents to be signed and sealed this _____ day of _____, _____.

(Principal)

(Surety)

(Attorney-in-fact)

