

WHITMAN COUNTY PUBLIC WORKS SMALL WORKS WORKSHEET

PROJECT NAME: 2022 Bridge Lumber Supplies

DESCRIPTION: (Materials, Supplies, Equipment)

See attached specifications

All materials, equipment and supply costs, plus tax, should be included in the quote. **QUOTE MUST BE FOB COLFAX**

Delivery must be by: 8 weeks after award

QUOTES MUST BE RETURNED BY: Wednesday, March 9, 2022 by 5:00 p.m.

***Anticipated award/order placement for quoted materials will be on Thursday, March 10, 2022, upon receipt of satisfactory pricing.**

***If multiple loads are required for delivery, we would accept some or all of the 4"x12" untreated planks as soon as they are available.**

Contact: Brandon Kruger – Ext. 5203

brandon.kruger@co.whitman.wa.us

Whitman County Public Works: (509) 397-4622 FAX (509) 397-6210

**WHITMAN COUNTY IS REQUESTING QUOTES FOR
2022 BRIDGE LUMBER SUPPLIES**

ITEM: 2022 Bridge Lumber and Sign Posts as Specified

F.O.B. Colfax, Washington

SPECIFICATIONS: All of the lumber shall be No. 1 or better structural grade Douglas Fir

All treated timber shall be fully incised and treated ACZA .60, in accordance with AWPAs Standards of the State of Washington Standard Specifications Manual of 2022 (English) for lumber and timbers, for bridges, structural members, decking, etc.

BRIDGE LUMBER

UNTREATED DOUGLAS FIR NO. 1, GREEN, ROUGH

QUANTITY	SIZE	DESCRIPTION	EACH	TOTAL
48 or two units @ 24 ea	4" x 12" x 20'	Untreated Rough		
24 or one unit @ 24 ea	4" x 12" x 24'	Untreated Rough		
24 or one unit @ 24 ea	4" x 12" x 26'	Untreated Rough		

TREATED ACZA .60 DOUGLAS FIR NO. 1, S4S, FREE OF HEART

QUANTITY	SIZE	DESCRIPTION	EACH	TOTAL
182 or two units @ 91 ea	4" x 4" x 14'	Treated S4S		

TREATED ACZA .60 DOUGLAS FIR NO. 1, FSR, FREE OF HEART

QUANTITY	SIZE	DESCRIPTION	EACH	TOTAL
25	2" x 10" x 20'	Treated FSR		
24	2" x 12" x 20'	Treated FSR		

ALL LUMBER MUST BE BANDED TOGETHER BY SIZE IN UNITS OR BY QUANTITIES ORDERED.

Sub-Total _____

Washington State Sales Tax _____

TOTAL _____